

VERIFICATION REPORT AND CERTIFICATION STATEMENT

Of Dongdongtan 9MWp Solar PV Project

(GS Ref. No. 2680)

Monitoring period #1: 08/12/2013 - 31/03/2015

Report No. A+SH_SYST_02915 Gs

Client: Carbon Invcap International Trading Co., Ltd.

DATE: 21/05/2015

Report No.	Date of first issue	Revision No.	Date of this revision
A+SH_SYST_02915 Gs	17/05/2015	01.1	21/05/2015
Subject	First periodical verification of a GS project		
Client	Carbon Invcap International Trading Co., Ltd.		
Project Title	Dongdongtan 9MWp Solar PV Project		
Project Participants	Three Gorges New Energy Jiuquan Power Generation Co., Ltd. (Project Owner) Carbon Invcap International Trading Co., Ltd. (Buyer)		
Project Location	Dongdongtan Area, Suzhou District, Jiuquan City, Gansu Province, P. R. of China Geographic coordinates: East longitude 98°32'09'' and North latitude 39°36'10''		
Contact Person	Dr. Zheng Zhaoning		
Operational Unit	Three Gorges New Energy Jiuquan Power Generation Co., Ltd.		
Monitoring period:		08/12/2013 - 31/03/2015	
Published Monitoring Report (version/date)		Version 01 / 01/04/2015	
Final Monitoring Report (version/date)		Version 02 / 16/05/2015	
Published GS SUSTAINABILITY MONITORING REPORT (version/date)		Version 01 / 01/04/2015 (same document with MR)	
Final GS Monitoring Report (version/date)		Version 02 / 16/05/2015 (same document with MR)	
Applied Methodology/Version		AMS-I.D Version 17.0	
Scope		1	
Technical Area		1.2	
Registered PDD and Passport:		PDD Version 05 / 08/05/2014 Passport Version 05 / 08/05/2014	
Summary:			
LGAI Technological Center, S.A. (hereafter referred to as Applus+ LGAI) has been contracted by Carbon Invcap International Trading Co., Ltd. to perform the first periodical verification of Dongdongtan 9MWp Solar PV Project (GS Ref. No. 2680) applying the methodology AMS-I.D Version 17.0. The management of Three Gorges New Energy Jiuquan Power Generation Co., Ltd. is responsible for the preparation of the GHG emissions data and the reported GHG emission reductions.			
A desk review and a site visit have been conducted to verify the data submitted in the monitoring report. Applus+ LGAI confirms the following has been reviewed:			
(a) The registered PDD and Passport, including the monitoring plan and the corresponding validation report;			
(b) Monitoring report(s);			

- (c) Validation Report;
- (d) The applied monitoring methodology;
- (e) Relevant decisions, clarifications and guidance from the CMP and the CDM Executive Board;
- (f) The Gold Standard Toolkit Version 2.2 and related Annex.
- (g) All information and references relevant to the project activity's resulting in emission reductions.

The purpose of the Project activity is to install 36,036 pieces of the polycrystalline silicon solar cell modules with unit capacity of 250 Wp to generate clean renewable electricity with zero emissions. The total installed capacity of the Project is 9.009 MWp.

Applus+ LGAI confirms that the project is implemented in accordance with the validated and registered PDD and Passport. The monitoring plan complies with the applied methodology AMS-I.D Version 17.0 and the Gold Standard Toolkit Version 2.2, the monitoring has been carried out in accordance with the monitoring plan. The monitoring system is in place and the emission reductions are calculated without material misstatements. Our opinion relates to the projects GHG emissions and the resulting GHG emission reductions reported and related to the valid and registered project baseline and monitoring and its associated documents. Based on the information reviewed and evaluated Applus+ LGAI confirms that the implementation of the project has resulted in **15,330** tCO₂e emission reductions during period 08/12/2013 - 31/03/2015.

Assessment team	Role	Organization
Hanshen (Denny) Xue	Lead Auditor / Team Leader	Applus+ LGAI, Shanghai

ABBREVIATIONS

ACM	Approved Consolidated Methodology
AM	Approved Methodology
AMS	Approved Methodology Small Scale
Applus+ LGAI	LGAI Technological Center, S.A. (Applus)
BM	Build Margin
CAR	Corrective Action Request
CDM	Clean Development Mechanism
CDM EB	CDM Executive Board
CER	Certified Emission Reduction
CM	Combined Margin
CMP	Conference of the Parties serving as the Meeting of the Parties to the Kyoto Protocol
DNA	Designated National Authority
DOE	Designated Operational Entity
EF	Emission Factor
EIA	Environmental Impact Assessment
ER	Emission Reduction
FAR	Forward Action Request
FSR	Feasibility Study Report
GHG	Greenhouse Gas(es)
GS	Gold Standard
IPCC	Intergovernmental Panel on Climate Change
IRL	Information Reference List
IRR	Internal Rate of Return
KP	Kyoto Protocol
MP	Monitoring Plan
MR	Monitoring Report
NGO	Non Governmental Organisation
NWPG	Northwest China Power Grid
TAC	Gold Standard Technical Advisory Committee
OM	Operational Margin
PDD	Project Design Document
PP	Project Participant
UNFCCC	United Nations Framework Convention for Climate Change
VVS	Validation and Verification Standard

TABLE OF CONTENT

1.	INTRODUCTION	1
1.1.-	Objective	1
1.2.-	Scope	1
1.3.-	Description of the Project Activity:	1
2.	METHODOLOGY	3
2.1.-	Review of Documentation	4
2.2.-	On-site Assessment and follow-up Interviews	4
2.3.-	Quality of Evidences	5
2.4.-	Reporting of Findings.....	5
2.5.-	Internal Quality Control.....	6
3.	VERIFICATION FINDINGS.....	7
3.1.-	FARs from Validation / Previous Verification	7
3.2.-	Project Implementation in accordance with the registered Project Design Document ..	7
3.3.-	Compliance of the Monitoring Plan with the Monitoring Methodology	8
3.4.-	Completeness of Monitoring	8
3.5.-	Parameter not monitored	9
3.6.-	Assessment of Data and Calculation of Greenhouse Gas Emission Reductions	9
3.7.-	Management and Operational System.....	12
3.8.-	Assessment of Sustainable Monitoring	13
4.	SUMMARY OF FINDINGS.....	17
5.	REFERENCE	18
6.	VERIFICATION STATEMENT	19

Annex 1: Verification Checklist and Resolution of Audit Findings

1. INTRODUCTION

1.1.- Objective

LGAI Technological Center, S.A. (hereafter referred to as Applus+ LGAI) has been contracted by Carbon Invcap International Trading Co., Ltd. to perform the first periodical verification of Dongdongtan 9MWp Solar PV Project (GS Ref. No. 2680) applying the methodology AMS-I.D Version 17.0 /6/ and the Gold Standard Toolkit Version 2.2 /9/. Gold Standard projects must undergo periodic audits and verification of emission reductions as the basis for issuance of Gold Standard VERs.

The objective of the verification work is to comply with the requirements of paragraph 62 of the CDM Modalities and Procedures as well as the Gold Standard Toolkit Version 2.2 /9/. According to this assessment Applus+ LGAI shall:

- ensure that the project activity has been implemented and operated as per the registered PDD and Passport "Dongdongtan 9MWp Solar PV Project" version 05, dated 08/05/2014 /3/ /4/, and that all physical features (technology, project equipment, monitoring and metering equipment) of the project are in place;
- ensure that the published MR and other supporting documents provided are complete, verifiable and in accordance with applicable VVS /8/ and Gold Standard requirements;
- ensure that the actual monitoring systems and procedures comply with the monitoring systems and procedures described in the monitoring plan and the approved methodology;
- evaluate the data recorded and stored as per the Grid connected renewable electricity generation, AMS-I.D Version 17.0 /6/.

1.2.- Scope

The verification scope encompasses an independent and objective review and ex-post determination of the monitored reductions in GHG emissions by the DOE. The verification is based on the submitted monitoring report, the validated and registered PDD and Passport as well as its validation report, the applied monitoring methodology, relevant decisions, clarifications and guidance from the CMP and the EB, The Gold Standard Toolkit Version 2.2 and any other information and references relevant to the project activity's resulting emission reductions. These documents are reviewed against the requirements of the Kyoto Protocol, the CDM Modalities and Procedures, The Gold Standard Toolkit Version 2.2 and related rules and guidance.

Based on the requirements in the VVS version 09.0 /8/ as well as the Gold Standard Toolkit Version 2.2 /9/, Applus+ LGAI has applied a rule-based approach for the verification of the project. The principles of accuracy, completeness, relevance, reliability and credibility were combined with a conservative approach to establish a traceable and transparent verification opinion.

The verification considers both quantitative and qualitative information on emission reductions. The verification also considers the monitoring of sustainable parameters.

The verification is not meant to provide any consultancy towards the client. However, stated requests for clarifications, corrective and/or forward actions may provide input for improvement of the monitoring activities.

1.3.- Description of the Project Activity:

Project activity:	Dongdongtan 9MWp Solar PV Project
Gold Standard registration number:	2680

Project Participants: Three Gorges New Energy Jiuquan Power Generation Co., Ltd. (Project Owner)
Carbon Invcap International Trading Co., Ltd. (Buyer)

Location of the project: Dongdongtan Area, Suzhou District, Jiuquan City, Gansu Province, P. R. of China

Geographic coordinates:
East longitude 98°32'09'' and North latitude 39°36'10''

Date of registration: 28/04/2014

Starting date of the crediting period: 08/12/2013

Dongdongtan 9MWp Solar PV Project (hereafter referred to as "the project") is located at Jiuquan City, Gansu Province, P. R. of China.

The purpose of the Project activity is to install 36,036 pieces of the polycrystalline silicon solar cell modules with unit capacity of 250 Wp to generate clean renewable electricity with zero emissions. The total installed capacity of the Project is 9.009 MWp. The project will contribute to the reduction of GHG emission by displacing part of the electricity from Northwest China Power Grid (NWPG) which is dominated by fossil fuel-fired power plants.

2. METHODOLOGY

Applus+ LGAI's approach to the verification is a two-stage process.

In the 1st stage, Applus+ LGAI completed a strategic review and risk assessment of the projects activities and processes in order to gain a full understanding of:

- Activities associated with all the sources contributing to the project emissions and emission reductions, including leakage if relevant;
- Protocols used to estimate or measure GHG emissions from these sources;
- Collection and handling of data;
- Controls on the collection and handling of data;
- Means of verifying reported data; and
- Compilation of the monitoring report.

Applus+ LGAI used a periodical Verification Checklist which, based on the risk-based assessment of the parameters and data collection and handling processes for each of those parameters, describes the verification approach and the sampling plan.

In the 2nd stage, using the Verification Checklist, Applus+ LGAI verified the implementation of the monitoring plan and the data presented in the Monitoring Report for the period in question. This involved a site visit and a desk review of the Monitoring Report. This Verification Report describes the findings of this assessment.

Assessment team

According to the sectoral scopes / technical area and experiences in the sectoral or national business environment, Applus+ LGAI has composed a project assessment team in accordance with the appointment rules in Applus+ LGAI complying with EB's requirements. The composition of assessment team has to be approved by the Applus+ LGAI ensuring that the required skills are covered by the team. The four qualification levels for team members that are assigned by formal appointment rules as below:

- Leader Auditor (LA)
- Auditor (A)
- Auditor Trainee (T)
- Technical Experts (E)

It is required that the sectoral scope / technical area linked to the methodology has to be covered by the assessment team.

Name	Qualification	Coverage of scope	Coverage of technical Area	Host country experience	Attendance to the On-Site Assessment
<i>Hanshen (Denny) Xue</i>	<i>LA</i>	<i>Y</i>	<i>Y</i>	<i>Y</i>	<i>Y</i>

Intermediate Technical Reviewer:

- Meng (Simon) Shen

Technical Reviewer:

- Miquel SITJES CABANAS

The curricula vitae of the DOE's validation team members are provided below:

Hanshen (Denny) Xue (Master Degree in Environmental Engineering, Bachelor Degree in Thermal Engineering) is a lead auditor appointed by Applus+ LGAI for the GHG project assessment. He is based on Shanghai. He has 1.5 years of work experiences in CDM project development. Before he joined Applus+ LGAI, he has been worked for Shanghai Chuanji Investment and Management which is a CDM consultancy company as a project manager for CDM project development.

Meng (Simon) Shen (Master Degree in Thermal Energy Engineering, Bachelor Degree in Environmental Engineering) has been appointed as a Technical Reviewer by Applus+ LGAI for the GHG project assessment. He is based in Shanghai. He has several years of work experience in environmental protection field. Before he joined Applus+ LGAI, he had been worked for TÜV SÜD as a GHG Validator/Verifier and ISO 9001/14001 Lead Auditor for 3.5 years.

Miquel SITJES CABANAS (B. Sc. degree in Chemistry 1975, Universidad de Barcelona – Spain). He has 15 years of experience in a Spanish chemical group company specialized in the manufacturing of raw chemical products, where he worked as the Manager of Quality Control, Production Manager and Environmental Manager. He also worked in the Spanish pharmaceutical industry for 7 years as Quality, Manufacturing and Environmental Manager. He has been working in the Applus+ LGAI Technological Centre since 1999: he started working there as an auditor (quality, environment, CDM, VCS, greenhouse gas verification and others) and since 2006 he has been the Systems Certification Technical Manager.

2.1.- Review of Documentation

The Monitoring Report version 01 /1/ was submitted to DOE before the verification activities started. The MR was assessed based on all the relevant documents. The aim of the assessment in the desk review was to:

- verify the completeness of the data and the information presented in the MR;
- check the compliance of the MR with respect to the monitoring plan depicted in the registered PDD and Passport, verify that the applied methodology was carried out. Particular attention to the frequency of measurements, the quality of the metering equipment including calibration requirements, and the quality assurance and quality control procedures was paid;
- evaluate the data management and the quality assurance and quality control system in the context of their influence on the generation and reporting of emission reductions.

A complete list of documents reviewed is available in chapter 6 of this report.

2.2.- On-site Assessment and follow-up Interviews

As a part of the verification, the on-site inspection has been performed by the assessment team.

Location: Dongdongtan Area, Suzhou District, Jiuquan City, Gansu Province, P. R. of China		
Date: 14/05/2015 - 15/05/2015		
Li Binqi	General Manager	Three Gorges New Energy Jiuquan Power Generation Co., Ltd.
Zhao Deshou	Engineer	Three Gorges New Energy Jiuquan Power Generation Co., Ltd.
Ma Xiaolong	Engineer	Three Gorges New Energy Jiuquan Power Generation Co., Ltd.

Yang Zhiwen	Section Chief	DRC of Jiuquan City
Wang Xiaoping	Villager	Shahe Village
Luo Jinhua	Villager	Shahe Village
Xia Yue	Project Manager	Goldchina Consultancy International Co., Ltd.

The objective of the on-site assessment is to:

- confirm the implementation and operation of the project;
- review the data flow for generating, aggregating and reporting the monitoring parameters;
- confirm the correct implementation of procedures for operations and data collection;
- cross-check the information provided in the MR documentation with other sources;
- check the monitoring equipment against the requirements of the PDD, Passport and the approved methodology, including calibrations, maintenance, etc.;
- review the calculations and assumptions used to obtain the GHG data and ER;
- identify if the quality control and quality assurance procedures are in place to prevent or correct errors or omissions in the reported parameters.

2.3.-Quality of Evidences

Sufficient evidence covering the full verification period in the required frequency is available to verify the figures stated in the final MR. The source of the evidences will be discussed in section 3 of this report. Specific cross-checks have been done in cases that further sources were available. The monitoring report's figures were checked by the assessment team against the raw data. The data collection system meets the requirements of the monitoring plan as per the methodology.

2.4.-Reporting of Findings

As an outcome of the verification process, the assessment team can raise different types of findings.

Where a non-conformance arises the assessment team shall raise a Corrective Action Request (CAR). A CAR is issued, where:

- Non-compliance with the monitoring plan or methodology are found in monitoring and reporting and has not been sufficiently documented by the project participants, or if the evidence provided to prove conformity is insufficient;
- Modifications to the implementation, operation and monitoring of the registered project activity has not been sufficiently documented by the project participants;
- Mistakes have been made in applying assumptions, data or calculations of emission reductions that will impact the quantity of emission reductions;
- Issues identified in a FAR during validation to be verified during verification or previous verification(s) have not been resolved by the project participants.

The assessment team shall raise a Clarification Request (CR) if information is insufficient or not clear enough to determine whether the applicable GS requirements have been met.

All CARs and CRs raised during verification shall be resolved prior to submitting a request for issuance.

Forward Action Requests (FARs) may be raised during verification for actions where the monitoring and reporting require attention and/or adjustment for the next verification period.

All CARs, CRs and FARs for this verification period are included in Section 5 of the verification checklist in the annex 1 of the report.

2.5.-Internal Quality Control

As a final step of verification, the final documentation including the verification report have to undergo an internal quality control by the Technical Reviewer. Each report has to be finally approved either by the DOE's Technical Manager or the Deputy. In case one of these two persons is part of the assessment team, the approval can only be given by the person who is not a part of the assessment team. If the documents have been satisfactorily approved, the Request for Issuance is submitted to the GS Registry along with the relevant documents.

3. VERIFICATION FINDINGS

In the following sections, the results of the verification are stated. The verification results related to the project performance as documented and described in the registered PDD (dated 08/05/2014, version 05) /3/, registered Passport (dated 08/05/2014, version 05) and Monitoring Report (dated 16/05/2015, version 02) /1/. The verification findings for each verification subject are presented below.

3.1.-FARs from Validation / Previous Verification

As this is the first periodical verification, after checking validation report /5/, there is no FARs requested.

3.2.-Project Implementation in accordance with the registered Project Design Document

The project activity was fully implemented according to the description presented in the registered PDD and Passport. The assessment team confirms, through the visual inspection that all physical features of the proposed project activity including data collecting systems and storage have been implemented in accordance with the registered PDD.

The technical features of the equipments have been verified by the assessment team during site visit by checking nameplate of main equipment /10/ which is detailed listed below:

	Item	Unit	Project
Solar cell module	Type		YL250P-29b
	Number		36,036
	Rated Max. Power	Wp	250
	Rated Voltage	V	30.4
	Rated Current	A	8.24
	Open Circuit voltage	V	38.4
	Short Circuit current	A	8.79
	Lifetime	year	25
Inverter	Type		SG500MX
	Number		18
	Rated Output power	kW	500
	Rated Output voltage	V	3~315
	Rated Output frequency	HZ	50

The project activity was in normal operational and the same has been confirmed on-site by checking Operation log /22/. The Project construction was commenced on 01/09/2013, and the operation was started on 08/12/2013 confirmed by checking validation report /5/ and operation log /22/.

The project was registered at 28/04/2014 as confirmed by the mail sent by Gold Standard, according to the Gold Standard Toolkit Version 2.2 /9/, for retroactive project, the start date of the crediting period could be extend to two years before the date for the registration, therefore,

as the project started operation on 08/12/2013, then the crediting period of the project started at 08/12/2013.

By comparing the actual ER claimed in this monitoring period with the estimate in the registered PDD, the actual emission reductions (15,330 tCO₂e) are lower than what is stated in the PDD (i.e. 16,237 tCO₂e) which will not lead to a substantial increment of the ER in this period

Applus+ LGAI confirms that none of the data affects the additionality, scale or applicability of the project. There's no post registration change has been occurred during this monitoring period.

3.3.-Compliance of the Monitoring Plan with the Monitoring Methodology

The monitoring plan is in accordance with the approved methodology AMS-I.D Version 17.0 /6/, applied by the proposed GS project activity. No deviation, correction or permanent change to the monitoring plan has been requested.

3.4.-Completeness of Monitoring

The monitoring has been carried out in accordance with the monitoring plan contained in the registered PDD. All parameters were monitored and determined as per the monitoring plan which is listed in below table:

Meth/tool	PDD	MR	Compliance?
EG _{facility,y}	EG _{facility ,y}	EG _{facility ,y}	Yes.

The verification of the parameters required by the monitoring plan is provided as follows:

Data / Parameter:	EG _{facility ,y}		
Data unit:	MWh		
Description:	Quantity of net electricity generation supplied of the Project to the grid in year y		
Purpose of the data:	Calculation of baseline emissions		
Parameter value:	17,891.072		
Source of data used:	Monthly Reading Record /15/ based on M1, ETNs /16/ issued by the grid company are used for the calculation.		
Information flow:	There are 2 meters installed in the outlet of main transformer of a Substation (M1 as main meter and M1' as backup meter). Both meters are used to monitor net electricity exported to the grid. Net electricity exported to the grid is continuous monitoring, hourly measurement and at least monthly recording. At 24:00 of the last day of every month, the raw data of meter reading of main meter are recorded by the project owner and form Monthly Reading Record /15/, and then send to the power grid company, after the confirmation of power grid company, the power grid company will issue ETNs /16/. Then the conservative value between the Monthly Reading Record (MRR) /15/ and ETNs /16/ issued by the power grid company would be used for ER calculation. All these have been confirmed by site visit.		
Monitoring method, frequency and equipments:	The parameter was measured continuously, hourly measurement and at least monthly recording by 2 electricity meters (M1 and M1'). All information of M1 and M1' meter are listed and verified by site visit and checking calibration certificate, see below:		
	Meter	Model	Serial Number
	M1	Mk6E	213211182
			Accuracy
			0.2s

	M1'	Mk6E	213211183	0.2s
Calibration:	Meters	Calibration date	Valid until	Certification Institution
	M1 /18/	17/11/2013	16/11/2014	Electric energy measurement test center of Gansu Power Grid Company /19/
		07/11/2014	06/11/2015	Electric energy measurement test center of Jiayuguan Power Grid Company /19/
	M1' /18/	17/11/2013	16/11/2014	Electric energy measurement test center of Gansu Power Grid Company /19/
		07/11/2014	06/11/2015	Electric energy measurement test center of Jiayuguan Power Grid Company /19/
	Electric energy measurement test center of Gansu Power Grid Company /19/ : (Gan)Faji(2011) No.62055 Valid since 26/01/2011 to 25/01/2016 Electric energy measurement test center of Jiayuguan Power Grid Company /19/: (Gan)Zhuanji(2010) No.62059 Valid since 29/11/2010 to 28/11/2014			
QA/QC procedure:	Electronic and paper records will be kept for a minimum of two years after the end of the crediting period.			
Means of verification:	Data of the parameter was verified by checking Monthly Reading Record /15/ based on 2 meters and ETNs /16/. All data is in line with Monthly Reading Record /15/ based on 2 meters and ETNs /16/; Information flow was verified by checking Monthly Reading Record /15/ based on 2 meters and ETNs /16/. All information are consistent; Monitoring method was verified by site visit, checking calibration certificate /18/, all monitoring method meets the description in the PDD; Calibration was verified by checking calibration certificate /18/ and Accreditation certificate /19/, all monitoring equipment meets the requirement indicated in the PDD.			
Cross-check:	Monthly Reading Record /15/ based on raw data is crosschecked with ETNs /16/. All data are logically consistent and conservative data are used to in the ER calculation.			

3.5.- Parameter not monitored

Below data has been verified against the data sources and the PDD.

Parameter title	Data	Source
EF _{grid,CM,y}	0.856875	Chinese Regional Grid Baseline Emission Factors 2013 /11/

Applus+ LGAI has verified the defaulted figures which are not monitored in crediting period and confirmed that the figures are consistent with their sources.

3.6.-Assessment of Data and Calculation of Greenhouse Gas Emission Reductions

As a result of verification of the ER calculation process, the assessment team confirmed that all the parameters required for the determination of the emission reductions have been included in the Monitoring report Version 02 /1/ and ER calculation spreadsheet /2/ and are consistent with the applied methodology AMS-I.D Version 17.0 /6/, Tool to calculate the emission factor for an

electricity system Version 04.0 /7/ and the monitoring plan contained in the registered PDD /3/. The parameters are complete in this monitoring period.

After verifying the reported figures with the raw data sources, it's confirmed that the values of the parameters from the raw data sources are consistent with those quoted in the Monitoring report Version 02 /1/ and ER calculation spreadsheet /2/. The verification process for the same has been clearly described in section 3.4 of the report. See below for the detailed data:

Baseline emissions:

Electricity exported to the grid

Data and parameters monitored	Electricity exported to the grid				
Monitoring Period	Starting Data of Meter Readings kWh A	End Data of Meter Readings kWh B	MRRs MWh $C = (B - A) * 14,000^1$	ETNs MWh D	Conservative value used in the calculation MWh $E = \text{Min} (C, D)$
08/12/2013-31/12/2013	0	26.351	368.914	360.992	360.992
2013 Sum			368.914	360.992	360.992
01/01/2014-31/01/2014	26.351	108.486	1,149.890	1,128.000	1,128.000
01/02/2014-28/02/2014	108.486	180.727	1,011.374	988.992	988.992
01/03/2014-31/03/2014	180.727	287.474	1,494.458	1,456.992	1,456.992
01/04/2014-30/04/2014	287.474	378.276	1,271.228	1,247.008	1,247.008
01/05/2014-31/05/2014	378.276	484.604	1,488.592	1,446.016	1,446.016
01/06/2014-30/06/2014	484.604	574.981	1,265.278	1,236.992	1,236.992
01/07/2014-31/07/2014	574.981	639.008	896.378	868.992	868.992
01/08/2014-31/08/2014	639.008	738.758	1,396.500	1,371.008	1,371.008
01/09/2014-30/09/2014	738.758	830.973	1,291.010	1,260.000	1,260.000
01/10/2014-31/10/2014	830.973	924.533	1,309.840	1,275.936	1,275.936
01/11/2014-30/11/2014	924.533	989.816	913.962	891.680	891.680
01/12/2014-31/12/2014	989.816	1,061.120	998.256	978.496	978.496
2014 Sum			14,486.766	14,150.112	14,150.112
01/01/2015-31/01/2015	1,061.120	1,140.822	1,115.828	1,082.816	1,082.816
01/02/2015-28/02/2015	1,140.822	1,215.646	1,047.536	1,025.056	1,025.056
01/03/2015-31/03/2015	1,215.646	1,314.884	1,389.332	1,361.824	1,361.824
2015 Sum			3,552.696	3,469.696	3,469.696
Sum			18,408.376	17,980.800	17,980.800

1. The multiplying power of the meter is 14,000

Electricity imported from the grid

Data and parameters monitored	Electricity imported from the grid				
Monitoring Period	Starting Data of Meter Readings kWh F	End Data of Meter Readings kWh G	MRRs MWh $H = (G - F) * 14,000^1$	ETNs MWh I	Conservative value used in the calculation MWh $J = \text{Max} (H, I)$

08/12/2013-31/12/2013	0	0.407	5.698	5.856	5.856
2013 Sum			5.698	5.856	5.856
01/01/2014-31/01/2014	0.407	0.828	5.894	6.080	6.080
01/02/2014-28/02/2014	0.828	1.151	4.522	4.672	4.672
01/03/2014-31/03/2014	1.151	1.450	4.186	4.320	4.320
01/04/2014-30/04/2014	1.450	1.755	4.270	4.416	4.416
01/05/2014-31/05/2014	1.755	2.092	4.718	4.832	4.832
01/06/2014-30/06/2014	2.092	2.396	4.256	4.352	4.352
01/07/2014-31/07/2014	2.396	2.748	4.928	5.056	5.056
01/08/2014-31/08/2014	2.748	3.081	4.662	4.768	4.768
01/09/2014-30/09/2014	3.081	3.423	4.788	4.896	4.896
01/10/2014-31/10/2014	3.423	3.809	5.404	5.504	5.504
01/11/2014-30/11/2014	3.809	4.304	6.930	7.072	7.072
01/12/2014-31/12/2014	4.304	4.854	7.700	7.936	7.936
2014 Sum			62.258	63.904	63.904
01/01/2015-31/01/2015	4.854	5.401	7.658	7.904	7.904
01/02/2015-28/02/2015	5.401	5.848	6.258	6.400	6.400
01/03/2015-31/03/2015	5.848	6.244	5.544	5.664	5.664
2015 Sum			19.460	19.968	19.968
Sum			87.416	89.728	89.728

- The multiplying power of the meter is 14,000

Quantity of net electricity generation supplied of the Project to the grid in year y

Monitoring Period	Electricity exported to the grid MWh	Electricity imported from the grid MWh	Quantity of net electricity generation supplied of the Project to the grid in year y MWh	$EF_{grid,CM,y}$ CO ₂ e/MWh	BE_y tCO ₂ e
08/12/2013-31/12/2013	360.992	5.856	355.136	0.856875	304
01/01/2014-31/12/2014	14,150.112	63.904	14,086.208		12,070
01/01/2015-31/03/2015	3,469.696	19.968	3,449.728		2,956
Total	17,980.800	89.728	17,891.072		15,330

Therefore, the net electricity generation supplied is determined as 17,891.072 MWh. As $EF_{grid,CM,y}$ is fix as 0.856875 tCO₂e/MWh, then:

$$\text{Then, } BE_y = 17,891.072 * 0.856875 = 15,330 \text{ tCO}_2\text{e}$$

Project emissions:

The project is a solar power project, no fossil fuel will be consumed according to the methodology AMS-I.D /6/, then, according to registered PDD, $PE_y = 0$ tCO₂e

Leakage:

According to AMS-I.D Version 17.0 /6/, if energy generating equipment is transferred from another activity, leakage is to be considered. As a newly built project, the equipments of the

project are all new but the equipment transfer from other activities. Then this part of leakage should be considered as zero.

In summary, $LE_y = 0 \text{ tCO}_2\text{e}$

Emission reductions:

$$ER = BE_y - PE_y - LE_y = 15,330 \text{ tCO}_2\text{e} - 0 \text{ tCO}_2\text{e} - 0 \text{ tCO}_2\text{e} = 15,330 \text{ tCO}_2\text{e}$$

The calculation tool, i.e. the ER calculation spreadsheet /2/ clearly and transparently describes the calculation of emission reductions. The ER calculation spreadsheet /2/ is indicated with the issuing date and revision number. The assessment team re-produced the calculation process and confirmed that the methods and formulae used to obtain the baseline, project and leakage emissions are appropriate. The calculation has been done in accordance with the methods and formulae described in the registered monitoring plan and applicable methodology.

The reported data have been cross-checked against other sources available as explained above in section 3.4 of the report.

Applus+ LGAI checked all registries including VCS (<http://www.vcsprojectdatabase.org/>) and REC (<http://www.epa.gov/greenpower/gpmarket/tracking.htm>), there are no double counting for this monitor period for the project. Also in the MR, the project owner made a declaration that states no RECs are been issued.

The assessment team confirms that all the assumptions, emission factors and default values (ex-ante values) from PDD have been correctly justified. All the emission factors and default values are explicitly mentioned in the monitoring report.

3.7.- Management and Operational System

The responsibilities of data measurement, collection, verifying, archiving etc. have been clearly defined in the Project Operation Manual /12/. The data related to ER calculation as well as data monitoring, collection process etc. have been internally reviewed by the management of the Monitoring team regularly. The responsibility of each function is consistent with the monitoring plan in the registered PDD.

- Ms. Wang Hongye as Office director is full charge of issues related to GS VER project ;
- Mr. Li Wei is charge of the GS sustainable development indicators monitoring;
- Mr. Wang Yaxi is in charge of equipment maintenance, data checking, archiving and managing;
- Mr. Ma Xiaolong is in charge of collecting data required by the checking activity, including meter readings records, electricity sales records and purchase records;
- Ms. Xia Yue from the Goldchina Consultancy International Co., Ltd. is responsible for preparing the Monitoring Report and ER calculation.

The information flow of each parameter has been verified by the assessment team via interviewing with responsible personnel and checking with the Project Operation Manual /12/. The details of information flow of each parameter are described in annex 1 of the verification report.

It's verified during the on-site verification, the monitoring procedure as well as the internal quality management and control procedures are stipulated in the Project Operation Manual /12/. The procedure are issued and approved by the top management. The monitoring personnel have been interviewed by the assessment team and it's confirmed that the monitoring is implemented as per the procedure. Also the training record and work certificate /13/ has been checked by the assessment team and it is confirmed that the monitoring personnel are get sufficient train to perform the monitoring.

All the data and documents, either hard copies or electric copies, will be kept for two years after the end of the last crediting period or the last issuance of GS VERs for this Project, whichever occurs later.

3.8.-Assessment of Sustainable Monitoring

In the Registered Passport Version 05 /4/, 5 indicators are chosen for the monitoring of sustainable monitoring for the project:

Meth/tool	Passport	MR	Compliance?
Air Quality	Air Quality	Air Quality	Yes
Water quality and quantity	Water quality and quantity	Water quality and quantity	Yes
Other pollutants	Other pollutants	Other pollutants	Yes
Quality of employment	Quality of employment	Quality of employment	Yes
Quantitative employment and income generation	Quantitative employment and income generation	Quantitative employment and income generation	Yes

The verification of the parameters required by the monitoring plan is provided as follows:

Indicator:	Air Quality
Chosen parameter:	Indirect parameter of "Total clean and renewable electricity supplied by the Project" is measured in order to calculate the concentrations of SO ₂ and NO _x , as multiplied by default national emission factor from the Chinese government
Parameter value:	17,891.072 MWh
Mitigation Measures:	Spraying water at construction sites, transporting material under tarpaulins.
Data Source:	Monthly Reading Record /15/ based on M1, ETNs /16/ issued by the grid company, Record for water spraying /23/.
Original situation of parameter:	Equivalent electricity supplied by NWPG which is generated by the operation of grid-connected power plants and by the addition of new generation sources into the grid.
Baseline situation of parameter:	Equivalent electricity supplied by NWPG which is generated by the operation of grid-connected power plants and by the addition of new generation sources into the grid.
Target achieved?	Yes, bases on online data, the SO ₂ and NO _x that could be generated in the baseline scenario are calculated as 41,149 kg and 46,517 kg tons respectively. After checking the Record for water spraying /23/ during the construction period, Questionnaires for environmental survey and interviewing with the local residents, the mitigation measure has been implemented well according to the GS passport; the impact of the Project to local air quality is negligible.
Procedure of monitoring:	The net electricity supplied by the project will be continuously measured by electricity meters. Please refer to table in the 3.4. Water spray was recorded during the construction period. Also Questionnaires for environmental survey /24/ are checked to confirm that the villagers around are satisfied with water sprayed status
Means of verification:	Monthly Reading Record /15/ based on M1, ETNs /16/ are checked to determine the net electricity generated by the project activity. Record for water spraying /23/ and Questionnaires for environmental survey /24/ are checked to determine the water sprayed status during the construction period.

Cross-check:	Not applicable
--------------	----------------

Indicator:	Water quality and quantity
Chosen parameter:	Not applicable
Data Source:	Not applicable
Parameter value:	Not applicable
Mitigation Measures:	Wastewater is treated through wastewater treatment facility, and then used as greening water.
Original situation of parameter:	Not applicable
Baseline situation of parameter:	Not applicable
Target achieved?	The waste water was treated, and then re-use as the greening water after site visit confirmation. Also by checking Questionnaires for environmental survey /24/, it is confirmed that the impact of the Project to local water quality and quantity is negligible.
Procedure of monitoring:	Check the wastewater treatment facility, Questionnaires for environmental survey and interview with the local residents to verify if the waste water was treated, and then re-use as the greening water
Means of verification:	After checking Record for waste water treatment during the construction period /26/, Questionnaires for environmental survey /24/ and interview with the local resident, it is confirmed that waste water were well treated during the construction period. During the site visit, it is able to confirm that wastewater treatment system are used for waste water treatment and re-use as the greening water.
Cross-check:	Not applicable

Indicator:	Other pollutants
Chosen parameter:	Not applicable
Data Source:	Not applicable
Parameter value:	Not applicable
Mitigation Measures:	Domestic solid waste will be collected together and periodically transferred to the local waste disposal plant for further treatment. The wasted equipment, such as the solar cell panel, will be collected together and transferred to the manufacturer.
Original situation of parameter:	Not applicable
Baseline situation of parameter:	Not applicable
Target achieved?	Yes
Procedure of monitoring:	Check the domestic solid waste collecting device, the wasted equipment collecting place and interview with local residents.
Means of verification:	After checking domestic solid waste collection device, Record for solid waste treatment /25/ and Questionnaires for environmental survey /24/ as well interview, it is confirmed for both domestic solid waste and wasted equipment are treated according to the requirement in the GS passport during operation

	and construction period.
Cross-check:	Not applicable

Indicator:	Quality of employment
Chosen parameter:	Training of staff
Parameter value:	Not applicable
Data Source:	Training Record /13/
Mitigation Measures:	Not applicable as indicator scored positive
Original situation of parameter:	Local people have no such opportunities to be trained on the technology and the monitoring of the plant operation, and the emergency and safety procedures.
Baseline situation of parameter:	Local people have no such opportunities to be trained on the technology and the monitoring of the plant operation, and the emergency and safety procedures.
Target achieved?	Yes, the staffs have accepted a series of training on the technology and the monitoring of the plant operation, and the emergency and safety procedures.
Procedure of monitoring:	The training records for all the employees
Means of verification:	By checking all the training records /13/, it is confirmed that the project owner provide sufficient training for the employee for skill and safety training. Also some interviews were made with employee and confirmed that they are receiving a lot of trainings.
Cross-check:	Not applicable

Indicator:	Quantitative employment and income generation
Chosen parameter:	Number of jobs created in the operations of the Project and their salary levels.
Data Source:	Statement for salary of employee /14/
Parameter value:	8 long-term work positions for local people have been created with 60,000 RMB yearly salaries for every employee
Mitigation Measures:	Not applicable as indicator scored positive
Original situation of parameter:	Local people have no such job opportunities from the Project, and their income has no increase.
Baseline situation of parameter:	In the baseline, local people have no such job opportunities from the project, and their income has no increase.
Target achieved?	Yes. 8 long-term work positions for local people have been created with 60,000 RMB yearly salaries for every employee.
Procedure of monitoring:	The project owner records the quantity of the work position and salary monthly. Salary and number of position would be checked monthly
Means of verification:	After checking Statement for salary of employee /14/, it is confirmed that 8 long-term work positions for local people have been created with 60,000 RMB yearly salaries for every employee. Also some interview with employee and general manager of the project owner was made to confirm the authentic of the information. Also, after checking China Statistical Yearbook 2013 /20/, it is found the average salary of the project activity is higher than the value of Gansu province.

Cross-check:	Not applicable
--------------	----------------

In Summary, it is Applus+ LGAI's opinion that the monitoring of the project owner regarding to sustainability is in line with requirement of the Gold Standard Toolkit Version 2.2 /9/

4. **SUMMARY OF FINDINGS**

The assessment team can confirm that the published MR and related documents are complete and verifiable in accordance with the GS requirements. All the findings that were raised by the assessment team, the responses by the PPs and the conclusion from the team are presented in section 5 of Annex 1. The means of verification and resulting changes in the MR or related documents are identified in the following tables:

Findings
CR#1: Please provide more information of M1 and M1' including the model in the MR.
Means of verification
After site visit, it is confirmed that correct information of M1 and M1' has been included in the MR.
Changes in the MR or related documents
More information of M1 and M1' has been included in the MR.

Findings
CR#2: Please clarify how quantity of net electricity generation supplied of the project activity to the grid in year y is monitored and the information flow of the data.
Means of verification
After site visit and checking MRR and ETNs of the project, it is confirmed that the meter readings of the electricity meter for electricity exported and imported at 24:00 of last day of each month would be record by project owner then forming MMRs then confirmed by power grid company by issue ETNs. The conservative value between MRR and ETNs would be used for ER calculation.
Changes in the MR or related documents
No change

5. REFERENCE

- /1/ Monitoring Report Version 01 dated 01/04/2015 and Monitoring Report Version 02 dated 16/05/2015
- /2/ ER calculation spreadsheet
- /3/ Registered PDD Version 05 dated 08/05/2014
- /4/ Registered Passport Version 05 dated 08/05/2014
- /5/ Gs Validation Report issued by TÜV Rheinland dated 12/05/2014 Version 04 Report No. 01 997 9105077913
- /6/ AMS-I.D Version 17.0 - Grid connected renewable electricity generation
- /7/ Tool to calculate the emission factor for an electricity system Version 04.0
- /8/ Validation and Verification Standard Version 09.0
- /9/ The Gold Standard Toolkit Version 2.2
- /10/ Nameplate of main equipment
- /11/ Chinese Regional Grid Baseline Emission Factors 2013
<http://cdm.ccchina.gov.cn/Detail.aspx?newsId=41386&TId=3>
- /12/ Project Operation Manual issued by project owner for project
- /13/ Training record and work certificate
- /14/ Statement for salary of employee issued by the project owner
- /15/ Monthly Reading Record of M1 covering the monitoring period
- /16/ ETNs covering the monitoring period for both electricity exported and imported
- /17/ Calibration Certificate for M1 and M1' covering the monitoring period issued by Electric energy measurement test center of Jiayuguan Power Grid Company covering 07/11/2014 to 06/11/2015
- /18/ Calibration Certificate for M1 and M1' covering the monitoring period issued by Electric energy measurement test center of Gansu Power Grid Company covering 17/11/2013 to 16/11/2014
- /19/ Accreditation of Electric energy measurement test center of Gansu Power Grid Company valid from 26/01/2011 to 25/01/2016
Accreditation of Electric energy measurement test center of Jiayuguan Power Grid Company valid from 29/11/2010 to 28/11/2014
- /20/ China Statistical Yearbook 2013
- /21/ Waste Handle Report under the operation and construction period
- /22/ Operation log
- /23/ Record for water spraying during the construction period
- /24/ Questionnaires for environmental survey
- /25/ Record for solid waste treatment during the construction and operation period
- /26/ Record for waste water treatment during the construction period

6. VERIFICATION STATEMENT

Applus+ LGAI has been engaged by Carbon Invcap International Trading Co., Ltd. to perform the first periodical verification of the Dongdongtan 9MWp Solar PV Project (GS Ref. No. 2680).

The management of Carbon Invcap International Trading Co., Ltd. is responsible for the preparation of the GHG emissions data and the reported GHG emissions reductions on the basis set out within the project's Monitoring Plan in the registered PDD version 05 completed on 08/05/2014, registered Passport version 05 completed on 08/05/2014 and the applied methodology AMS-I.D Version 17.0.

Our verification approach was based on the requirements as defined under the Kyoto Protocol, Marrakesh accord, as well as those defined by the CDM Executive Board and Gold Standard. Our approach is risk-based, drawing on an understanding of the risks associated with reporting GHG emissions data and the controls in place to mitigate these. The verification can confirm that:

- the project is operated as planned and described in the project design document and passport approved by the EB and GS;*
- the monitoring plan is as per the applied methodology;*
- the monitoring in Monitoring Report is as per the PDD and Passport and the monitoring plan approved by the EB and GS;*
- the development and maintenance of records and reporting procedures are in accordance with the registered monitoring plan;*
- the installed equipment being essential for generating emission reduction runs reliably and is calibrated appropriately;*
- the monitoring system is in place and generates GHG emission reductions data;*
- the GHG emission reductions are calculated without material misstatements.*

In our opinion, the GHG emission reductions for Dongdongtan 9MWp Solar PV Project for the monitoring period 08/12/2013 - 31/03/2015 as reported in Monitoring Report, prepared on the basis of the project's Monitoring Plan are fairly stated.

Based on the information we have seen and evaluated, we confirm the following statement:

Reporting period: From 08/12/2013 to 31/03/2015


Verified emissions in the above reporting period:

<i>Leakage emissions</i>	<i>0 tCO₂ equivalents</i>
<i>Project emissions</i>	<i>0 tCO₂ equivalents</i>
<i>Baseline emissions</i>	<i>15,330 tCO₂ equivalents</i>
<i>Emission reductions in 2013</i>	<i>304 tCO₂ equivalents</i>
<i>Emission reductions in 2014</i>	<i>12,070 tCO₂ equivalents</i>
<i>Emission reductions in 2015</i>	<i>2,956 tCO₂ equivalents</i>
<i>Emission reductions</i>	<i>15,330 tCO₂ equivalents</i>


Signature

Date: 21/05/2015

Assessment team: Hanshen (Denny) Xue (Team Leader / Leader Auditor)



DOE Representative: Miquel Sitjes Cabanas (CDM Technical Manager)



B.U. Systems Certification Area Manager: Juan Sendín Caballero



Annex 1:

**VERIFICATION CHECKLIST
for GS PROJECT ACTIVITY**

PROJECT TITLE: Dongdongtan 9MWp Solar PV Project

REFERENCE NO: A+SH_SYST_02915

VERSION NO. 01

CLIENT NAME: Carbon Invcap International Trading Co., Ltd.

ASSESSMENT TEAM:

Lead Auditor: Hanshen (Denny) Xue

Technical Expert: Hanshen (Denny) Xue

1. Compliance of Project Activity Implementation

1.1. Basic information

Location												
	Real situation			Consistency of PDD/Passport			Consistency of MR			Conclusion		
Address:	Dongdongtan Area, Suzhou District, Jiuquan City, Gansu Province, P. R. of China			Dongdongtan Area, Suzhou District, Jiuquan City, Gansu Province, P. R. of China			Dongdongtan Area, Suzhou District, Jiuquan City, Gansu Province, P. R. of China			OK		
GPS coordinates:	East longitude 98°32'09" and North latitude 39°32'10"			East longitude 98°32'09" and North latitude 39°32'10"			East longitude 98°32'09" and North latitude 39°32'10"			OK		
Technical specification of main Equipment												
	Real situation			Consistency of PDD/Passport			Consistency of MR			Conclusion		
Description	The purpose of the Magang Project is to install 36,036 pieces of the polycrystalline silicon solar cell modules with unit capacity of 250Wp to generate clean renewable electricity with zero emissions.			The purpose of the Magang Project is to install 36,036 pieces of the polycrystalline silicon solar cell modules with unit capacity of 250Wp to generate clean renewable electricity with zero emissions.			The purpose of the Magang Project is to install 36,036 pieces of the polycrystalline silicon solar cell modules with unit capacity of 250Wp to generate clean renewable electricity with zero emissions.			OK		
Component 1: Solar cell module	Type		YL250P-29b	Type		YL250P-29b	Type		YL250P-29b	OK		
	Number		36,036	Number		36,036	Number		36,036			
	Rated Max. Power	Wp	250	Rated Max. Power	Wp	250	Rated Max. Power	Wp	250			
	Rated Voltage	V	30.4	Rated Voltage	V	30.4	Rated Voltage	V	30.4			
	Rated Current	A	8.24	Rated Current	A	8.24	Rated Current	A	8.24			
	Open Circuit volt-	V	38.4									

	age			Open voltage	Circuit	V	38.4	Open voltage	Circuit	V	38.4	
	Short Circuit current	A	8.79	Short current	Circuit	A	8.79	Short current	Circuit	A	8.79	
	Lifetime	year	25	Lifetime	year	25	Lifetime	year	25			
Component 2: Inverter	Type		SG500MX	Type		SG500MX	Type		SG500MX	OK		
	Number		18	Number		18	Number		18			
	Rated Output power	kW	500	Rated power	Output	kW	500	Rated power	Output		kW	500
	Rated Output voltage	V	3~315	Rated voltage	Output	V	3~315	Rated voltage	Output		V	3~315
	Rated Output frequency	HZ	50	Rated frequency	Output	HZ	50	Rated frequency	Output		HZ	50
Operation Status during verification												
	Real situation			Consistency of PDD/PASSPORT			Consistency of MR			Conclusion		
Actual Operation Status	The Project construction was commenced on 01/09/2013, and the operation was started on 08/12/2013, during this monitoring period, the project is under normal operation.			The Project construction was commenced on 01/09/2013, and the operation was started on 08/12/2013, during this monitoring period, the project is under normal operation.			The Project construction was commenced on 01/09/2013, and the operation was started on 08/12/2013, during this monitoring period, the project is under normal operation.			OK		

1.2. Organization

Project Participant (s)		
	Verified Situation	Conclusion
Entity / Responsible person:	Through site visit, the verification team confirms Ms. Wang Hongye is responsible for supervising the whole GS issues in the project activity.	OK

Project management:	- Ms. Wang Hongye as Office director is full charge of issues related to GS VER project ; - Mr. Li Wei is charge of the GS sustainable development indicators monitoring; - Mr. Wang Yaxi is in charge of equipment maintenance, data checking, archiving and managing; - Mr. Ma Xiaolong is in charge of collecting data required by the checking activity, including meter readings records, electricity sales records and purchase records; - Ms. Xia Yue from the Goldchina Consultancy International Co., Ltd. is responsible for preparing the Monitoring Report and ER calculation.	OK
---------------------	--	----

1.3. Quality Management System

General aspects of the Quality Management System		
	Verified Situation	Conclusion
Quality Management Manual:	After site visit, it is confirmed that Project Operation Manual is well followed.	OK
Responsibilities:	- Ms. Wang Hongye as Office director is full charge of issues related to GS VER project ; - Mr. Li Wei is charge of the GS sustainable development indicators monitoring; - Mr. Wang Yaxi is in charge of equipment maintenance, data checking, archiving and managing; - Mr. Ma Xiaolong is in charge of collecting data required by the checking activity, including meter readings records, electricity sales records and purchase records; - Ms. Xia Yue from the Goldchina Consultancy International Co., Ltd. is responsible for preparing the Monitoring Report and ER calculation.	OK
Qualification and Training:	After checking training record, it is confirmed that training are appropriated held by the project owner	OK
Implementation of QM-system	After site visit, it is confirmed that Project Operation Manual is well followed.	OK

1.4. Remaining FARs from previous Verifications (or forwarded issues of validation report)

Remaining Requests from Previous Verifications	Summary of project owner response	Assessment team Conclusion
Forward action request No. 1: None	-N.A	-OK

2. Monitoring Plan of Parameters

2.1. Parameters

Parameters					
Meth/tool	PDD	MR	Included in below table	Compliance	Conclusion
Quantity of net electricity generation supplied of the Project to the grid in year y	Quantity of net electricity generation supplied of the Project to the grid in year y	Quantity of net electricity generation supplied of the Project to the grid in year y	Section 2.2 Table 1	Yes	OK

2.2. Parameters measured directly with instruments

Table 1: Quantity of net electricity generated supplied to the grid in year y

Parameter and instrumentation Information					
	PDD	Meth/Tool	MR	Verified	Conclusion
Parameter title:	Quantity of net electricity generation supplied of the Project to the grid in year y	Quantity of net electricity generation supplied of the Project to the grid in year y	Quantity of net electricity generation supplied of the Project to the grid in year y	Fully consistent	OK

Parameter ID (if available):	EG _{facility,y}	EG _{facility,y}	EG _{facility,y}	Fully consistent	OK
Data Unit:	MWh	MWh	MWh	Fully consistent	OK
Monitoring frequency (reading):	Continuously monitored	Continuously monitored	Continuously monitored	Fully consistent	OK
Monitoring frequency (recording):	Monthly Record	Monthly Record	Monthly Record	Fully consistent	OK
Calibration requirements:	Technical administrative code of electric energy metering (DL/T 448-2000)	N.A	Technical administrative code of electric energy metering (DL/T 448-2000)	Although not mentioned in the methodology, it is assumed that the calibration should be at least once a year	OK
Uncertainty level:	N.A	N.A	N.A	Fully consistent	OK
Measurement Principle (if applicable):	N.A	N.A	N.A	Fully consistent	OK
	Technical aspects				Conclusion
Instrument Type:	Electricity Meter: M1, M1'				OK
Serial Number:	M1: 213211182 M1': 213211183				OK
Manufacturer Model Nr.:	CR#1: Please provide more information of M1, M1' including the model in the MR.				CR#1 OK
Specific Location:	M1 and M1' are both installed at outlet of the switch station.				OK
Measurement Range:	M1: 0.2s Backup M1': 0.2s				OK
Calibration of the instrument:	Meter	Calibration Date	Valid Date	OK	
	M1	17/11/2013	16/11/2014		
		07/11/2014	06/11/2015		
	M1'	17/11/2013	17/11/2014		
		06/11/2014	07/11/2015		

Accreditation of the calibration institute:	(Gan)Faji(2011)No.62055 Valid since 26/01/2011 to 25/01/2016 (Gan)Zhuanji(2010)No.62059 Valid since 29/11/2010 to 28/11/2014	OK
Gaps in operating time of instrument:	Period: N.A	OK
	Default value used: N.A	OK
	Justification: N.A	OK
	QA/QC aspects	Conclusion
Source of data:	Source: The conservative value between the MRR and ETNs. CR#2: Please clarify how quantity of net electricity generation supplied of the project activity to the grid in year y is monitored and the information flow of the data.	CR#2 OK
	Procedures: Project operation manual	OK
	Implementation of procedure: By site visit, the verification team confirms Project operation manual has been corrected performed for the project activity.	OK
	Responsibility: The project owner and power grid company is responsible for collecting the raw data	OK
Archiving of raw data and protection measures:	All the data will be kept until two years after the end of credit period.	OK
Data transfer and protection of input data for calculations:	Refer to CR#2.	CR#2 OK
	Quality of evidence	Conclusion
Completeness of data:	The MRRs and statement are checked to verify the completeness of the data.	OK
Data verification:	Consistency of raw data with calculation tool: Yes	OK
	Consistency of calculation tool with monitoring report: Yes	OK
Crosscheck (if available):	MRRs based on raw data is crosschecked with ETNs. All data are logically consistent.	OK

2.3. Other parameters not included in the methodology/tool but included in the PDD

N.A

2.4. Data and parameter not monitored in the monitoring period but available at validation

Data and parameter not monitored in the monitoring period but available at validation					
	Meth/Tool	PDD or approved MP	MR	Verified	Conclusion
Parameter title	EF _{grid,CM,y}	EF _{grid,CM,y}	EF _{grid,CM,y}	Fully consistent	OK
Data Unit	tCO ₂ /MWh	tCO ₂ /MWh	tCO ₂ /MWh	Fully consistent	OK
Parameter Description	CM Emission factor	CM Emission factor of NWPG	CM Emission factor of NWPG	Fully consistent	OK
Source of data	N.A.	Public data from Chinese NDRC	Registered PDD	Fully consistent	OK
Value	N.A.	0.856875	0.856875	Fully consistent	OK

3. Sustainability Monitoring Plan

3.1. Indicators

Indicators					
GS requirements	Passport	MR	Included in below table	Compliance	Conclusion
Air Quality	Air Quality	Air Quality	Section 3.2 Table 1	Yes, all information are compliance	OK
Water quality and quantity	Water quality and quantity	Water quality and quantity	Section 3.2 Table 2	Yes, all information are compliance	OK
Other pollutants	Other pollutants	Other pollutants	Section 3.2 Table 3	Yes, all information are compliance	OK
Quality of employment	Quality of employment	Quality of employment	Section 3.2 Table 4	Yes, all information are	OK

Indicators					
GS requirements	Passport	MR	Included in below table	Compliance	Conclusion
				compliance	
Quantitative employment and income generation	Quantitative employment and income generation	Quantitative employment and income generation	Section 3.2 Table 5	Yes, all information are compliance	OK

3.2. Indicators monitored

Table 1 Air Quality

Indicators Information					
	Passport	GS requirements	MR	Verified	Conclusion
Indicator title:	Air Quality	Air Quality	Air Quality	Fully consistent	OK
Indicator Nr. (if available):	1	N.A	1	Fully consistent	OK
Chosen parameter:	Indirect parameter of "Total clean and renewable electricity supplied by the Project" is measured in order to calculate the concentrations of SO ₂ and NO _x , as multiplied by default national emission factor from the Chinese government	N.A	Indirect parameter of "Total clean and renewable electricity supplied by the Project" is measured in order to calculate the concentrations of SO ₂ and NO _x , as multiplied by default national emission factor from the Chinese government	Fully consistent	OK
Monitoring measures (how):	Check the spraying water logging and interview with the local residents; and the net electricity supplied by the Project	N.A	Check the spraying water logging and interview with the local residents; and the net electricity supplied by the Project	Fully consistent	OK

	will be continuously measured by electricity meters		will be continuously measured by electricity		
Monitoring frequency (when):	The monitoring of the mitigation measure will be done once during the first verification; and the net electricity supplied by the Project will be continuously measured and monthly recorded.	N.A	The monitoring of the mitigation measure will be done once during the first verification; and the net electricity supplied by the Project will be continuously measured and monthly recorded.	Fully consistent	OK
Responsibility (by who):	Project Owner	N.A	Project Owner	Fully consistent	OK
	Technical aspects				Conclusion and IRL
Original situation of parameter:	Equivalent electricity supplied by NWPG which is generated by the operation of grid-connected power plants and by the addition of new generation sources into the grid.				OK
Baseline situation of parameter:	Equivalent electricity supplied by NWPG which is generated by the operation of grid-connected power plants and by the addition of new generation sources into the grid.				OK
Mitigation measures:	Spraying water at construction sites, transporting material under tarpaulins.				OK
The situation of the parameter at the stage of verification:	17,891.072MWh of clean electricity produced by the Project				OK
Target achieved?	Yes, based on online data, the SO ₂ and NO _x that could be generated in the baseline scenario are calculated as 41,149 kg and 46,517 kg tons respectively. After checking the spraying water log, Record for interview with local resident and interviewing with the local residents, the mitigation measure has been implemented well according to the GS passport; the impact of the Project to local air quality is negligible.				OK
	QA/QC aspects				Conclusion
Procedure of monitoring:	The net electricity supplied by the project will be continuously measured by electricity meters. Refer to the 2.2.1.				OK

Archiving of documents and protection measures:	All the data will be kept until two years after the end of credit period.	OK
	Quality of evidence	Conclusion
Means of verification:	Document Review and Interview	OK
Documents verified:	MRR and ETNs http://news.bjx.com.cn/html/20120606/364987.shtml Spraying water logging Record for interview with local resident	OK
Practice witnessed:	N.A	OK
Person interviewed:	The general manager of the project and local resident	OK
Crosscheck (if available):	N.A	OK

Table 2 Water quality and quantity

Indicators Information					
	Passport	GS requirements	MR	Verified	Conclusion
Indicator title:	Water quality and quantity	Water quality and quantity	Water quality and quantity	Fully consistent	OK
Indicator Nr. (if available):	2	N.A	2	Fully consistent	OK
Chosen parameter:	N.A	N.A	N.A	Fully consistent	OK
Monitoring measures (how):	Check the wastewater treatment facility and interview with the local residents.	N.A	Check the wastewater treatment facility and interview with the local residents.	Fully consistent	OK
Monitoring frequency (when):	Once for each monitoring period.	N.A	Once for each monitoring period.	Fully consistent	OK

Responsibility (by who):	The project owner	N.A	The project owner	Fully consistent	OK
	Technical aspects				Conclusion
Original situation of parameter:	Not applicable				OK
Baseline situation of parameter:	Not applicable				OK
Mitigation measures:	Wastewater is treated through wastewater treatment facility, and then used as greening water.				OK
The situation of the parameter at the stage of verification:	The waste water was treated, and then re-use as the greening water after site visit confirmation. Also by checking Record for interview with local resident, it is confirmed that the impact of the Project to local water quality and quantity is negligible.				OK
Target achieved?	Yes				OK
	QA/QC aspects				Conclusion
Procedure of monitoring:	Check the wastewater treatment facility, Record for interview with local resident and interview with the local residents to verify if the waste water was treated, and then re-use as the greening water				OK
Archiving of documents and protection measures:	All the data will be kept until two years after the end of credit period.				OK
	Quality of evidence				Conclusion
Means of verification:	Interview, Document Review and Site visit				OK
Documents verified:	Record for waste water treatment and Record for interview with local resident				OK
Practice witnessed:	The wastewater treatment system				OK
Person interviewed:	The general manager of the project and local resident				OK
Crosscheck (if available):	N.A				OK

Table 3 Other pollutants

Indicators Information

	Passport	GS requirements	MR	Verified	Conclusion
Indicator title:	Other pollutants	Other pollutants	Other pollutants	Fully consistent	OK
Indicator Nr. (if available):	3	N.A	3	Fully consistent	OK
Chosen parameter:	N.A	N.A	N.A	Fully consistent	OK
Monitoring measures (how):	Check the domestic solid waste collecting device, the wasted equipment collecting place and interview with local residents.	N.A	Check the domestic solid waste collecting device, the wasted equipment collecting place and interview with local residents.	Fully consistent	OK
Monitoring frequency (when):	Once for each monitoring period	N.A	Once for each monitoring period	Fully consistent	OK
Responsibility (by who):	The project owner	N.A	The project owner	Fully consistent	OK
	Technical aspects				Conclusion
Original situation of parameter:	N.A				OK
Baseline situation of parameter:	N.A				OK
Mitigation measures:	Domestic solid waste will be collected together and periodically transferred to the local waste disposal plant for further treatment. The wasted equipment, such as the solar cell panel, will be collected together and transferred to the manufacturer.				OK
The situation of the parameter at the stage of verification:	After checking domestic solid waste collection device, waste equipment treatment record and Record for interview with local resident as well interview, it is confirmed for both domestic solid waste and wasted equipment are treated according to the requirement in the GS passport during operation and construction period.				OK
Target achieved?	Yes				OK
	QA/QC aspects				Conclusion
Procedure of monitoring:	Domestic solid waste device, waste equipment treatment record and Record for interview with local resident				OK

	are checked, local resident are interviewed	
Archiving of documents and protection measures:	All the data will be kept until two years after the end of credit period.	OK
	Quality of evidence	Conclusion
Means of verification:	Document Review, Interview and Site visit	OK
Documents verified:	Waste Equipment Treatment record, Record for interview with local residents	OK
Practice witnessed:	Domestic solid waste treatment system	OK
Person interviewed:	The general manager of the project and Local Resident	OK
Crosscheck (if available):	N.A	OK

Table 4 Quality of employment

Indicators Information					
	Passport	GS requirements	MR	Verified	Conclusion and IRL
Indicator title:	Quality of employment	Quality of employment	Quality of employment	Fully consistent	OK
Indicator Nr. (if available):	4	N.A	4	Fully consistent	OK
Chosen parameter:	Training of staff	N.A	Training of staff	Fully consistent	OK
Monitoring measures (how):	The training records for all the employees	N.A	The training records for all the employees	Fully consistent	OK
Monitoring frequency (when):	Once for each monitoring period	N.A	Once for each monitoring period	Fully consistent	OK
Responsibility (by who):	Project owner	N.A	Project owner	Fully consistent	OK
	Technical aspects				Conclusion
Original situation of parameter:	Local people have no such opportunities to be trained on the technology and the monitoring of the plant operation, and the emergency and safety procedures.				OK

Baseline situation of parameter:	Local people have no such opportunities to be trained on the technology and the monitoring of the plant operation, and the emergency and safety procedures.	OK
Mitigation measures:	Not applicable as indicator scored positive	OK
The situation of the parameter at the stage of verification:	The staffs have accepted a series of training on the technology and the monitoring of the plant operation, and the emergency and safety procedures.	OK
Target achieved?	Yes	OK
	QA/QC aspects	Conclusion
Procedure of monitoring:	Checking training record	OK
Archiving of documents and protection measures:	All the data will be kept until two years after the end of credit period.	OK
	Quality of evidence	Conclusion
Means of verification:	Document Review, Interview and site visit	OK
Documents verified:	Training Record	OK
Practice witnessed:	Staffs are well trained on the technology and the monitoring of the plant operation, and the emergency and safety procedures.	OK
Person interviewed:	The general manager of the project and employees	OK
Crosscheck (if available):	N.A	OK

Table 5 Quantitative employment and income generation

Indicators Information					
	Passport	GS requirements	MR	Verified	Conclusion
Indicator title:	Quantitative employment and income generation	Quantitative employment and income generation	Quantitative employment and income generation	Fully consistent	OK
Indicator Nr. (if available):	5	N.A	5	Fully consistent	OK

Chosen parameter:	Number of jobs created in the operations of the Project and their salary levels.	N.A	Number of jobs created in the operations of the Project and their salary levels.	Fully consistent	OK
Monitoring measures (how):	HR records or report	N.A	HR records or report	Fully consistent	OK
Monitoring frequency (when):	Monthly	N.A	Monthly	Fully consistent	OK
Responsibility (by who):	Project owner	N.A	Project owner	Fully consistent	OK
	Technical aspects				Conclusion
Original situation of parameter:	Local people have no such job opportunities from the Project, and their income has no increase.				OK
Baseline situation of parameter:	In the baseline, local people have no such job opportunities from the project, and their income has no increase.				OK
Mitigation measures:	Not applicable as indicator scored positive				OK
The situation of the parameter at the stage of verification:	8 long-term work positions for local people have been created with at least 60,000 yearly salaries for every employee.				OK
Target achieved?	Yes				OK
	QA/QC aspects				Conclusion
Procedure of monitoring:	Salary and number of position would be checked monthly				OK
Archiving of documents and protection measures:	All the data will be kept until two years after the end of credit period.				OK
	Quality of evidence				Conclusion
Means of verification:	Document Review and Interview				OK
Documents verified:	HR record for salary				OK
Practice witnessed:	N.A				OK

Person interviewed:	The general manager of the project and employees	OK
Crosscheck (if available):	N.A	OK

4. Data Processing and ER calculation

Description of data processing from transferred data to final results in the calculation tool		
Step	Description	Conclusion
Consistency	All abbreviations and units are consistent with PDD, Passport or approved monitoring plan and Methodology and traceable to the raw data.	OK
Calculation Tool description	The calculation tool is clearly described and transparent. The issuing date and revision number is indicated. All formulae, intermediate steps and constants are described transparently including correct units and in compliance with the methodology and the PDD, Passport or approved monitoring plan.	OK
Elimination of not plausible data (if applicable)	N.A.	OK
Transformation from use-able data to input data for further calculation (if applicable)	N.A.	OK
Ex-ante data	Ex-ante data are in compliance with the PDD, Passport or approved monitoring plan and methodology/tool.	OK
Default parameter	Default parameter is in compliance with the PDD, Passport or approved monitoring plan and methodology/tool.	OK
Formulae check	All formulae included in the calculation tool are in compliance with the PDD or approved monitoring plan and methodology/tool.	OK
Rounding functions	Included rounding functions are correctly and conservatively applied.	OK
Calculation tool changes and protection measures	The tool is delivered to the verification team directly from people in charge of GS matters of the PPs and consulting company which ensure there are no unauthorized change happened. As this is the first periodic verification, no modification is done against last periodic verification.	OK

Reported data	The result of the calculation tool is consistent with the value in the MR.	OK
---------------	--	----

5. Additional assessment

5.1. Internal Review

Description and performance of internal review		
	Description	Conclusion
Procedure	N.A	OK
Documentation	N.A	OK
Responsibilities	N.A	OK

5.2. Peculiarities

Description of Peculiarities and unexpected Daily Events during the verification period		
	Description	Conclusion
Performance	The verification confirms there are no peculiarities occur during this monitoring period by checking archived data and site visit.	OK
Documentation	The verification confirms there are no peculiarities occur during this monitoring period by checking archived data and site visit.	OK
Measures	The verification confirms there are no peculiarities occur during this monitoring period by checking archived data and site visit.	OK

5.3. Further additional requirements

Description of additional requirements to be checked		
	Description	Conclusion
Compliance Environmental requirements	By interview with the local stakeholders, it is confirmed that the project meet the requirement for environment.	OK

5.4. Data Reporting

Description of the Monitoring Report		
	Comments and Results	Conclusion
Compliance with regulations	The monitoring report version 02 dated 16/05/2015 covering period from 08/12/2013 to 31/03/2015 considers all related regulations (e.g. requirements of the methodology and the monitoring report).	OK
Completeness and Transparency	The monitoring report version 02 dated 16/05/2015 covering period from 08/12/2013 to 31/03/2015 is complete and transparent.	OK
Correctness	All of the provided values are correctly transferred from the related and assessed sources (e.g. calculation tool).	OK

6. Compilation and Resolutions of CARs, CL/CRs and FARs

Type:	☐ CAR ☒ CL/CR ☐ FAR	Number:	#1
Raised by:	Denny (Hanshen) Xue	Ref. to checklist in above tables:	Table 2.2.1
Description of the audit finding	Date: 14/05/2015		
Please provide more information of M1 and M1' including the model in the MR.			
Project Participant's response	Date: 16/05/2015		
The model of the M1 and M1' was detailed in the revised MR.			
Documentation provided as evidence by Project Participant			
Meter picture			
Auditor's assessment comment	Date: 17/05/2015		
After site visit, it is confirmed that correct information of M1 and M1' has been included in the MR.			
Conclusion by Lead Auditor	Date: 17/05/2015		
CR#1 is closed out.			

Type:	☐ CAR ☒ CL/CR ☐ FAR	Number:	#2
Raised by:	Denny (Hanshen) Xue	Ref. to checklist in above tables:	Table 2.2.1
Description of the audit finding	Date: 14/05/2015		
Please clarify how quantity of net electricity generation supplied of the project activity to the grid in year y is monitored and the information flow of the data.			
Project Participant's response	Date: 16/05/2015		
The net electricity generation supplied to the grid was measured by electricity meter. The readings of the meters start from the first day of every month and end at 24:00 of the last day of every month were recorded in the meter reading records by the shift monitoring staffs, then the measured result was cross checked by the records for sold/purchased electricity, the conservative value was used. The meter reading records will be achieved in written form and kept for two years after the end of the last crediting period.			
Documentation provided as evidence by Project Participant			

Meter reading records, the records for sold/purchased electricity		
Auditor's assessment comment	Date:	17/05/2015
After site visit and checking MRR and ETNs of the project, it is confirmed that the meter readings of the electricity meter for electricity exported and imported at 24:00 of last day of each month would be record by project owner then forming MMRs then confirmed by power grid company by issue ETNs. The conservative value between MRR and ETNs would be used for ER calculation.		
Conclusion by Lead Auditor	Date:	17/05/2015
CR#2 is closed out.		