



**Verified Carbon
Standard**

FINAL VERIFICATION REPORT


“KUMKOY HYDROELECTRIC POWER PLANT, SAMSUN”



RINA Services S.p.A.

Project Title	Kumkoy Hydroelectric Power Plant, Samsun
Version	3.0Aa
Report ID	21XTMD41

Report Title	Final Report of “Kumkoy Hydroelectric Power Plant, Samsun”
Client	ENTEK Elektrik Uretimi A.S.
Pages	22
Date of Issue	31/01/2023 report issued

Prepared By	RINA Services S.p.A.
Contact	Address : Via Corsica, 12 – 16128 Genova, ITALY Telephone : +39 010 538 55 09 email : ghg.services@rina.org web site : www.rina.org
Approved By	Giovanni D'Angelo (Authorized officer signing for the DOE) Sustainability & Food Certification Compliance Unit 
Work Carried Out By	Tugce KIRATLI; VCS Team Leader, VCS Verifier, Technical Expert

Summary:

RINA Services S.p.A. (RINA), commissioned by ENTEK Elektrik Uretimi A.S., has verified the greenhouse gas emission reductions reported for the project activity “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, VCS Registration Reference N° 986, for the period 01/04/2019 to 02/03/2021, with regard to the relevant requirements for CDM and VCS activities.

The objective of the verification is to have an independent review ex post determination of the monitored reductions in GHG emission reductions, reported for the “Kumkoy Hydroelectric Power Plant, Samsun” project in Turkey for the period 01/04/2019 to 02/03/2021.

Verification was conducted using RINA procedures in line with the requirements specified in the VCS Version 4.1 Requirements, CDM M&P, the latest version of the CDM Validation and Verification Standard, and relevant decisions of the COP/MOP and the CDM EB and applying standard auditing techniques. The verification consisted of desk review, remote-site assessment and the resolution of outstanding issues and the issuance of the final verification report and certification.

The verification shall ensure that reported emission reductions are complete and accurate in accordance with applicable VCS Version 4.1 requirements, which refer to CDM rules, in order to be certified.

In conclusion, it is RINA's opinion that the project activity “Kumkoy Hydroelectric Power Plant, Samsun”, in “Turkey”, as described in the Monitoring Report version 03 of 19/01/2022, meets all relevant requirements for VCS and CDM activities and all relevant host Party criteria and correctly applies the baseline and monitoring methodology “ACM0002”, “Consolidated methodology for grid connected electricity generation”, version 13.0 of 11/05/2012. Hence, RINA is able to certify that the

emission reductions from the project during the monitoring period 01/04/2019 to 02/03/2021 amount to 83,484 tCO₂e.

CONTENTS

1	Introduction	5
1.1	Objective.....	5
1.2	Scope and Criteria	5
1.3	Level of Assurance.....	5
1.4	Summary Description of the Project	5
2	Verification Process.....	6
2.1	Method and Criteria.....	8
2.2	Document Review	8
2.3	Interviews	8
2.4	Site Inspections.....	10
2.5	Resolution of Findings	11
2.6	Eligibility for Validation Activities	13
3	Validation Findings.....	13
3.1	Participation under Other GHG Programs	13
3.2	Methodology Deviations.....	13
3.3	Project Description Deviations.....	13
3.4	Grouped Project	13
4	Verification Findings.....	13
4.1	Project Implementation Status	14
4.2	Safeguards	14
4.3	AFOLU-Specific Safeguards	15
4.4	Accuracy of GHG Emission Reduction and Removal Calculations	15
4.5	Quality of Evidence to Determine GHG Emission Reductions and Removals	15
4.6	Non-Permanence Risk Analysis.....	21
5	Verification conclusion	22

1 INTRODUCTION

1.1 Objective

The objective of the verification is to have an independent review ex post determination by a Designated Operational Entity (DOE) of the monitored reductions in GHG emissions that have occurred as a result of the registered VCS project activity during a defined monitoring period. Certification is the written assurance by the DOE that, during a specific time period, a proposed VCS project activity achieved the reductions in anthropogenic emissions by sources of GHGs as verified.

The objective of this verification/certification was to verify and certify emission reductions and effective implementation of the monitoring of sustainable development indicators and mitigation measures, reported for the “Kumkoy Hydroelectric Power Plant, Samsun” project in Turkey for the period 01/04/2019 to 02/03/2021.

1.2 Scope and Criteria

The verification scope is:

- to verify that actual monitoring systems and procedures are in compliance with the monitoring systems and procedures described in the monitoring plan;
- to evaluate the GHG emission reduction data and express a conclusion with a reasonable level of assurance about whether the reported GHG emission reduction data is free from material misstatement;
- to verify that reported GHG emission data is sufficiently supported by evidence;
- to evaluate whether all the mitigation measures have been effectively put in place according to the monitoring plan and that all the sustainable development indicators have been correctly monitored.

Verification shall ensure that reported emission reductions are complete and accurate in accordance with applicable VCS Version 4.1 requirements, which refer to CDM rules, in order to be certified.

UNFCCC criteria for CDM refer to Article 12 of the Kyoto Protocol, the CDM modalities and procedures, and the subsequent decisions by the CDM Executive Board.

Verification is not meant to provide any consultancy towards the project participants. However, stated requests for clarifications and/or corrective actions may have provided input for improvement of the monitoring.

1.3 Level of Assurance

All the revisions of the verification report, before being submitted to the client, were subjected to an independent internal technical review to confirm that all verification activities had been

completed according to the pertinent RINA instructions. All evidence had been confirmed during remote site visit with the invoices of electricity generation. The level of assurance is reasonable.

The technical review was performed by a technical reviewer(s) qualified in accordance with RINA's qualification scheme for VCS and CDM validation and verification. The verification team and the technical reviewers consist of the following personnel:

Role/Qualification	Last Name	First Name	Country
VCS Team Leader – VCS Verifier – Technical Expert	Kiratli	Tugce	Turkey
Independent Technical Reviewer	Singh	Vinay	India

1.4 Summary Description of the Project

ENTEK Elektrik Uretimi A.S. has commissioned RINA to carry out the verification and certification of emission reductions reported for the registered “Kumkoy Hydroelectric Power Plant, Samsun” project in Turkey, VCS Registration Reference N° 986, for the period 01/04/2019 to 02/03/2021.

The project is hydroelectric power plant located in Yesilirmak River in Black Sea Region, Samsun Province of Turkey.

The Project Activity utilizes the Yesilirmak river water in a run-of-river hydro power scheme to generate electricity with zero carbon emissions for the Turkish Power Grid. The project activity consists of 3 bulb-type turbines, with a total installed capacity of 17.5 MWe as confirmed through the Previous Verification Report [/21/](#). The generated electricity is transmitted to the National Electricity System through 31.5 kV Carsamba TM.

The GHG benefit of the project activity was only accounted under VCS. There are not any other RECs were being issued for the project activity. Furthermore, as a host country in Turkey such any programme like a government-regulated system or programme for the constraint and monetisation of GHG emissions (such as emissions trading scheme, cap and trade or carbon tax mechanisms) has not been implemented.

The generated electricity is supplied to the National Electricity Transmission Grid of Turkey.

Project Participant(s)	ENTEK Elektrik Uretimi A.S.		
Project Title	Kumkoy Hydroelectric Power Plant, Samsun		
Location of the project	Black Sea Region, Samsun Province of Turkey		
Methodology(ies)	“ACM0002”, “Consolidated methodology for grid connected electricity generation”, version 13.0 of 11/05/2012 /6/		
Sectoral Scope(s)	1	RINA's Technical Area(s)	1.2

Registered VCS PD	Version 2.1 of 28/02/2013
VCS Registration Reference No	986
Starting date of the crediting period	03/03/2011 (as confirmed through the registered VCS-PD /1/)
Project's crediting period	From 03/03/2011 to 02/03/2021
Monitoring period	01/04/2019 - 02/03/2021 (both days included)
Project documentation link	https://registry.verra.org/app/projectDetail/VCS/986

2 VERIFICATION PROCESS

The project was validated by TUV Rheinland on 01/03/2013 and it was registered under the VCS registration reference N° 986. This is the last verification assessment for the monitoring period 01/04/2019 to 02/03/2021 by RINA.

2.1 Method and Criteria

Verification was conducted using RINA procedures in line with the requirements specified in the VCS Version 4.1 Requirements, CDM M&P, the latest version of the CDM Validation and Verification Standard, and relevant decisions of the COP/MOP and the CDM EB and applying standard auditing techniques.

The verification consisted of the following three phases:

- Document review;
- On-site assessment (Remote Audit);

The resolution of outstanding issues and the issuance of the final verification report and certification.

2.2 Document Review

The monitoring report, version 03 of 19/01/2022 and previous versions /2/, the emission reduction calculations provided in the form of a spreadsheet, “Final_ER calculations_538 Kumkoy hydro_v04_10-12-2019.xlsx” version 04 of 10/12/2019 and previous versions /8/, the approved baseline and monitoring methodology ACM0002 version 13.0 /6/ and all the documentation provided to support the monitoring period /01 – 21/ were assessed as part of the verification. In addition, the VCS Project Description (VCS PD) /1/, in particular as regards the baseline estimations and the monitoring plan, and the Validation Report of 01/03/2013 /7/ for the project, were reviewed.

The following table lists the documentation that was reviewed during the verification.

/1/	Ekobil: VCS PD for “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, Version 2.1 of 28/02/2013
/2/	Seem Turkey: Monitoring report for “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, version 03 of 19/01/2022 Seem Turkey: Monitoring report for “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, version 02 of 27/11/2021 Seem Turkey: Monitoring report for “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, version 01 of 06/06/2021
/3/	VCS Verified Carbon Standard: VCS Program Guide, VCS Version 4 of 19/09/2019
/4/	VCS Verified Carbon Standard: VCS Standard, VCS Version 4.1 of 19/09/2019

/5/	VCS Verified Carbon Standard: Validation and Verification Manual, version 3.2 of 19/10/2016
/6/	CDM Executive Board: Baseline and monitoring methodology “ACM0002”, “Consolidated methodology for grid connected electricity generation”, version 13.0 of 11/05/2012
/7/	TUV Rheinland: Validation Report for “Kumkoy Hydroelectric Power Plant, Samsun” of 01/03/2013
/8/	Seem Turkey: Emission Reduction Calculation Spreadsheet “Final_ER calculations_538 Kumkoy hydro_v04_10-12-2019.xlsx” version 04 of 10/12/2019 Seem Turkey: Emission Reduction Calculation Spreadsheet “Final_ER calculations_538 Kumkoy hydro_v03_10-12-2019.xlsx” version 03 of 10/12/2019
/9/	VCS Verified Carbon Standard: VCS Verification Report Template Version 4 of 19/09/2019
/10/	CDM Executive Board: Methodological Tool “Tool to calculate the emission factor for an electricity system”, version 03.0.0 of 23/11/2012
/11/	Website: https://registry.verra.org/app/projectDetail/VCS/986 Argument: Verra Database Language: English; Retrieved on: 04/03/2022
/12/	Entek Enerji: Turbine Templates, submitted on 03/06/2021
/13/	Entek Enerji: Screenshot of Google Maps for reservoir area, submitted on 19/01/2022
/14/	EPIAS: Monthly Meter Reading Protocols for the monitoring period 01/04/2019 to 02/03/2021
/15/	TEIAS: Monthly Meter Reading Protocols for the monitoring period 01/04/2019 to 02/03/2021
/16/	The Turkish Ministry of Trade and Industry: Regulation of Metering and Testing of Metering Systems of 24/07/1994
/17/	Turkish Energy Market Regulatory Authority: Communiqué for Measurement Devices used in the Electricity Market of 22/03/2003
/18/	The Energy Market Regulatory Authority: Electricity Market Balancing and Settlement Regulation of 14/04/2009
/19/	Turkish Electricity Transmission Company (TEIAS): Meter Change Protocol of 20/10/2019 for electricity meters
/20/	Entek Enerji: Petitions from Kumkoy Village Mukhtar, of 08/07/2019
/21/	Re-Carbon: Previous Verification Report, report ID: 538 version 03 of 10/12/2019
/22/	Website of GS: https://registry.goldstandard.org/projects?q=kumkoy&page=1 , retrieved on 31/01/2023
/23/	Website of GCC: https://projects.globalcarboncouncil.com/pages/approved_projects , retrieved on 31/01/2023

2.3 Interviews

When the site visit date was approaching, as Turkey, there was a possibility of going out at certain times depending on the age range or curfew due to the pandemic. For this reason, all verification and validation activities were carried out remotely in order not to put any project in a difficult situation during the pandemic period.

Therefore, the Plant Manager was interviewed by phone during remote audit. To see how the monitoring procedures were implemented, the whole process was explained to the verification team. The carbon consultant was interviewed via videoconference about the monitoring report and related parameters. Whole process related emission reduction calculation was explained. The mukhtars were interviewed via phone. They confirmed that no grievance was announced by the stakeholders.

The key personnel interviewed, and the main topics of the interviews are summarized in the table below.

	Date	Name and Role	Organization	Topic
/a/	09/11/2021	Burcu BORAN <i>Carbon Consultant</i>	Seem Turkey	Monitoring plan Monitoring methodology Monitoring data Implementation status of the project
/b/	09/11/2021	Serkan DUNDAR <i>Project Responsible</i>	Entek Enerji	Monitoring equipment and operation Calibration certificates Emission Reductions calculation
/c/	09/11/2021	Tuncay SONKAYA <i>Mukhtar</i>	Kumkoy Village	Positive and negative impacts of the project activity
/d/	09/11/2021	Ekrem OZBEK <i>Stakeholder</i>	Kumkoy Village	Contact details of the project proponents
/e/	09/11/2021	Suleyman OZTURK <i>Stakeholder</i>	Kumkoy Village	Tail Water Local Employment

2.4 Site Inspections (Remote Audit)

On 09/11/2021, RINA performed a remote audit for the hydro power plant located in Samsun province of Turkey. During the video conference for the project, it was confirmed that all the equipment and the systems were accessible. RINA assessed the implementation and operation of the proposed project activity, reviewed the information flows for generating, aggregating and reporting the monitoring parameters, interviewed key personnel of the plant to confirm the operational and data collection procedures, cross-checked between information provided in the monitoring report and data plant, checked the monitoring equipment including calibration performance, reviewed calculations and assumptions made in determining the GHG data and emission reductions, checked the quality control and quality assurance procedures in place to prevent or identify and correct any errors or omissions in the reported monitoring parameters.

2.5 Resolution of Findings

The objective of this phase of the verification is to resolve any outstanding issues, which need to be clarified for RINA's positive conclusion on the monitoring report and emission reductions.

To guarantee transparency a verification protocol has been customized for the project. The protocol shows in a transparent manner the requirements, means of verification and the results from verifying the identified criteria. The verification protocol consists of three tables; the different columns in these tables are described in the figure below (see Figure 1). The completed verification protocol is enclosed in Appendix 4 to this report.

A corrective action request (CAR) is raised if one of the following occurs:

- Non-conformities with the monitoring plan or methodology are found in monitoring and reporting, or if the evidence provided to prove conformity is insufficient;
- Mistakes have been made in applying assumptions, data or calculations of emission reductions that will impair the estimate of emission reductions;
- Issues identified in a FAR during validation to be verified during verification have not been resolved by the project participants.

A clarification request (CR) is raised if information is insufficient or not clear enough to determine whether the applicable VCS requirements, which refer to CDM rules, have been met.

During this monitoring period, no CAR/CR is raised. All findings are closed during on videoconferences.

Figure 1 Verification protocol tables

Verification Protocol, Table 1 - Requirement checklist					
Checklist Question	Ref.	MoV	Comments	Draft Conclusion	Final Conclusion
Checklist questions organized in seven different sections.	Makes reference to documents where the answer to the checklist question or item is found.	Explain how conformance with the checklist question is investigated. Examples are document review (DR), interview or any other follow-up actions (I), cross checking (CC) with available information relating to projects, (N/A) means not applicable.	The discussion on how the conclusion is arrived at and the conclusion on the compliance with checklist question so far.	For CAR, CR and FAR see the definitions above.	OK is used if the information and evidence provided is adequate to demonstrate compliance with VCS requirements which refer to CDM rules.

Verification Protocol, Table 2: Resolution of Corrective Action Requests and Clarification			
Corrective action requests and/or clarification requests	Reference to Table 1	Response by project participants	Verification Conclusion
The CAR and/or CRs raised in table 1 are repeated here.	Reference to the checklist question number in Table 1 where the CAR or CR is explained.	The responses given by the project participants to address the CARs and/or CRs.	The verification team's assessment and final conclusion of the CARs and/or CRs.

Verification Protocol, Table 3 - Forward Action Requests		
Forward action request	Reference to Table 1	Response by project participants Verification Conclusion
The FAR raised in table 1 is repeated here.	Reference to the checklist question number in Table 1 where the FAR is explained.	Response by the project participants on how forward action request will be addressed.

2.5.1 Forward Action Requests

According to the previous verification Report [/21/](#), no FAR is raised.

2.6 Eligibility for Validation Activities

The project activity is registered under VCS registration reference Number 986 [/11/](#); hence this section is not applicable.

3 VALIDATION FINDINGS

In the registered VCS PD for “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, Version 2.1 of 28/02/2013 [/1/](#), the installed capacity is defined as 17.5 MWe as confirmed through the Previous Verification Report [/21/](#). The average electricity generation is estimated as 91,964 MWh as per the registered VCS PD [/1/](#). The additionality of the project activity is demonstrated by applying investment analysis registered VCS PD [/1/](#).

The project was validated by TUV Rheinland on 01/03/2013 [/7/](#) and it was registered under the VCS registration reference N° 986.

3.1 Participation under Other GHG Programs

The project activity is not participated under other GHG Programs as confirmed through the websites of the other standards [/22/](#) [/23/](#) [/11/](#).

3.2 Methodology Deviations

There are no methodology deviations applied during this monitoring period.

3.3 Project Description Deviations

There is no project description deviation in this monitoring period.

3.4 Grouped Project

This project is not a grouped project. Hence, this section is not applicable.

4 VERIFICATION FINDINGS

4.1 Project Implementation Status

It was verified during the remote audit conducted on 09/11/2021 that the proposed project activity has been implemented and it is in operation in accordance with the project activity described in the registered VCS PD /1/.

The project activity has been implemented in 1 phase. On 03/03/2011, the power plant has started operation with 3 units. The commissioning date was confirmed through the Previous Verification Report /21/. The crediting period starts on 03/03/2011.

The project activity consists of 3 bulb-type turbines, with a total installed capacity of 17.5 MWe as confirmed through the Previous Verification Report /21/. The project boundary in the registered VCS PD /1/ is in line with the actual project boundary. The generated electricity is fed to the national grid. The generated electricity is transmitted to the National Electricity System through 31.5 kV Carsamba TM. The geographic coordinates of the project activity are confirmed through the registered VCS-PD /1/.

There are not any material discrepancies between project implementation and the project description. It is verified that actual monitoring systems and procedures are in compliance with the monitoring systems and procedures described in the monitoring plan. The project activity is not participated or rejected under other GHG Programs as confirmed through the websites of the standard /11/. No GHG related environmental credits are applied to the Turkish power sector.

The GHG benefit of the project activity was only accounted under VCS. There are not any other RECs were being issued for the project activity. Furthermore, as a host country in Turkey such any programme like a government-regulated system or programme for the constraint and monetisation of GHG emissions (such as emissions trading scheme, cap and trade or carbon tax mechanisms) has not been implemented.

The project generates electricity from renewable energy sources using hydro as a power source and contributes to Turkey's increasing electricity demand with its sustainable and low-carbon technology. The project displaces the same amount of electricity produced by the grid dominated by fossil fuel power plants. The project contributes to SDG7 Economic and Clean Energy.

The Project contributes to improving the environmental situation in the region and in the country, as avoiding fossil fuel-based electricity will improve air quality and help reduce adverse effects on the climate. Sustainable and climate-friendly development is promoted through renewable technologies and hydro-based electricity. The project contributes to SDG13 Climate Action. While the project reduces emissions, technology transfer is also realized by utilizing hydroelectricity.

During the construction and operation period, the Project created employment opportunities for the local community. The project contributes to the economic development of the region by providing sustainable energy resources. The project provides employees with a safe and healthy work environment and is not complicit in exposing employees to unsafe or unhealthy work environments. Thus, the Project contributes to SDG8 Decent Work and Economic Growth.

It is verified by RINA that the project has been implemented as described in the VCS-PD.

4.2 Safeguards

4.2.1 No Net Harm

There isn't any negative environmental or socio-economic impact.

4.2.2 Local Stakeholder Consultation

The local stakeholder consultation was conducted in Kumkoy Village on 03/10/2007. For this monitoring period, stakeholders were interviewed by phone. It was learned that in general, the main form of communication between the local people and the project owner is face-to-face or by phone. They stated that in case of any problem, they can easily reach the responsible persons and convey their complaints. There are no complaints/compliance related to the project implementation during this monitoring period. This issue is confirmed with the petitions provided from Mukhtar. The contact details of the project responsible is provided and shared with all stakeholders.

4.3 AFOLU-Specific Safeguards

This project is not an "Agriculture, Forestry and Other Land Use (AFOLU)" project.

4.4 Accuracy of GHG Emission Reduction and Removal Calculations

The emission reduction calculations provided in the spreadsheet [/8/](#) have been verified to be correct and in line with the registered VCS PD [/1/](#).

According to the applied methodology "ACM0002", "Consolidated baseline methodology for grid-connected electricity from renewable sources", version 13.0 of 11/05/2012 [/6/](#), the emission reductions have been calculated based on the following formula:

$$ER_y = BE_y - PE_y - LE_y$$

Where:

BE_y = Baseline emissions in year y (tCO₂e/yr)

PE_y = Project emissions in year y (tCO₂e/yr)

LE_y = Leakage emissions in year y (tCO₂e/yr)

Baseline emissions

The baseline emissions include the CO₂ emissions from electricity generation in fossil fuel fired power plants that are displaced due to the project activity, multiplying the electricity supplied to the grid (MWh) with the combined margin CO₂ emission factor for grid connected power generation in year.

$$BE_y = EG_{PJ} \times EF_{grid,CM,y}$$

Where:

EG_{PJ} = Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the CDM project activity in year y (MWh/yr)

$EF_{grid,CM,y}$ = Combined margin CO₂ emissions factor in year y (tCO₂/MWh)

Project emissions

Project emissions from reservoir has been assumed to be 0 since the power density is larger than 10 W/m² as per the ACM0002 version 13 of 11/05/2012 /6/ as defined in the validated VCS PD /1/. In the registered VCS PD for “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, Version 2.1 of 28/02/2013 /1/, the power density has been calculated based on the only reservoir area. Power density is calculated accordingly in the Monitoring Report /2/. The power density is higher than 10 W/m²; therefore, project emissions are neglected.

Leakage emissions

The leakage emissions are assumed to be zero as per the ACM0002 version 13 of 11/05/2012 /6/ as defined in the registered VCS PD /1/.

The data presented in the monitoring report /2/ were assessed by reviewing in detail project documentation, collection of monitored data, observation of established monitoring and reporting practices and assessment of the reliability of monitoring equipment. Sufficient evidence was presented and verified by RINA for the reported emission reductions.

Parameters Available at Validation and Data Fixed Ex-ante

DATA/PARAMETER	Source of data	Reported value for the project period	Assessment/Observation
$EF_{grid,CM,y}$ Baseline emission factor	TEIAS statistics	0.53323 tCO ₂ /MWh	According to the approved methodology ACM0002 version 13.0, the combined emission factor has been determined using the ex-ante option and so it is not requested to monitor and recalculate the emission factors during the crediting period. The emission factor is determined to be 0.53323 tCO ₂ /MWh in the VCS PD /1/ and validation report /7/.

Parameters and Data Monitored

DATA/PARAMETER	EGPP-Gorss,y
Data Unit	MWh
Description	Quantity of electricity produced by the power plant, in y
Source of data	Meter Reading Forms
Description of measurement methods and procedures to be applied	The electricity generation figures are based on the TEIAS meter readings /15/ and the EPIAS records for Electricity Generation /14/ are used for crosscheck.
Frequency of monitoring/recording	Continuously monitoring and monthly recording
Value monitored	01/04/2019 – 31/12/2019: 71,708.29 MWh 01/01/2020 – 31/12/2020: 79,095.87 MWh 01/01/2021 – 02/03/2021: 6,161.8 MWh Total: 156,965.96 MWh
Monitoring equipment	Two electricity meters (one main meter and one backup meter) were installed at the project site. The old main meter was ACTARIS 53042294. The backup old meter was ACTARIS with serial number 53042295. The meters were changed on 20/10/2019. The new main meter is ITRON with serial number 84260361. The backup new meter is ITRON with serial number 84260362. The meters have the accuracy of 0.5s as confirmed through meter change protocol /19/ . The accuracy class of the meters complies with the “Communiqué for Measurement Devices used in the Electricity Market” /17/ .
QA/QC procedures to be applied	TEIAS is responsible for calibration and maintenance of the meters as per the registered VCS PD /1/ . The project owner has no control on the meters since the meters are sealed by the TEIAS as confirmed during the remote audit. If any major discrepancy occurs between the two meters, TEIAS performs necessary calibration. The new meters at the project site were calibrated by the TEIAS on 20/10/2019 as confirmed through the meter change protocol /19/ . As per the “Regulation of Metering and Testing of Metering Systems” /16/ , the meters shall be calibrated every 10 years, therefore the calibration of meters is deemed appropriate and in compliance with the national regulation. During on remote audit, it was confirmed that the meters are in place and functions well. During the monitoring period, no breakdown has been recorded.
Purpose of the data	To calculate the baseline emission value
Calculation method	The electricity generation and consumption are measured in line with the TEIAS rules and requirements /18/ . The electricity generation supplied to the grid and electricity consumption from the grid is stored by EPIAS on the web site. The Project owner has an ID and password to access this data on the web site. The collected data during the monitoring period will be kept by the project owner at least two years after end of the last

	crediting period as stated in the registered VCS PD /1/ and monitoring report /2/ in line with the ACM0002 version 13 of 20/08/2012 /6/ .
Comments	-

DATA/PARAMETER	EGPP-Self consumption,y
Data Unit	MWh
Description	Quantity of electricity imported by the power plant to the Grid for self-consumption, in year y
Source of data	Meter Reading Forms
Description of measurement methods and procedures to be applied	The electricity generation figures are based on the TEIAS meter readings /15/ and the EPIAS records for Electricity Generation /14/ are used for crosscheck.
Frequency of monitoring/recording	Continuously monitoring and monthly recording
Value monitored	01/04/2019 – 31/12/2019: 97.58 MWh 01/01/2020 – 31/12/2020: 225.67 MWh 01/01/2021 – 02/03/2021: 76.03 MWh Total: 399.28 MWh
Monitoring equipment	Two electricity meters (one main meter and one backup meter) were installed at the project site. The old main meter was ACTARIS 53042294. The backup old meter was ACTARIS with serial number 53042295. The meters were changed on 20/10/2019. The new main meter is ITRON with serial number 84260361. The backup new meter is ITRON with serial number 84260362. The meters have the accuracy of 0.5s as confirmed through meter change protocol /19/ . The accuracy class of the meters complies with the “Communiqué for Measurement Devices used in the Electricity Market” /17/ .
QA/QC procedures to be applied	TEIAS is responsible for calibration and maintenance of the meters as per the registered VCS PD /1/ . The project owner has no control on the meters since the meters are sealed by the TEIAS as confirmed during the remote audit. If any major discrepancy occurs between the two meters, TEIAS performs necessary calibration. The new meters at the project site were calibrated by the TEIAS on 20/10/2019 as confirmed through the meter change protocol /19/ . As per the “Regulation of Metering and Testing of Metering Systems” /16/ , the meters shall be calibrated every 10 years, therefore the calibration of meters is deemed appropriate and in compliance with the national regulation. During on remote audit, it was confirmed that the meters are in place and functions well. During the monitoring period, no breakdown has been recorded.
Purpose of the data	To calculate the baseline emission value

Calculation method	The electricity generation and consumption are measured in line with the TEIAS rules and requirements /18/. The electricity generation supplied to the grid and electricity consumption from the grid is stored by EPIAS on the web site. The Project owner has an ID and password to access this data on the web site. The collected data during the monitoring period will be kept by the project owner at least two years after end of the last crediting period as stated in the registered VCS PD /1/ and monitoring report /2/ in line with the ACM0002 version 13 of 20/08/2012 /6/.
Comments	-

DATA/PARAMETER	CapPJ
Data Unit	W
Description	Installed capacity of the hydro power plant after the implementation of the project activity
Source of data to be used	Project site computers with SCADA system and the turbine name plates
Value data for the monitoring period	17,50,000
Measuring and reporting frequency; recording procedure	Once for each monitoring period
Type of monitoring equipment and its accuracy	The parameter is monitored through the SCADA system of the Project Activity; therefore, measurement equipment is not used.
Calibration frequency/interval	NA
How were the values in the monitoring report verified and cross-checked?	The parameter is monitored through the Turbine Templates /12/ .
Does the data management (from monitoring equipment to emission reduction calculation) ensure correct transfer of data and reporting of emission reductions?	NA
If only partial data are available because activity levels or non-activity parameters have not been monitored in accordance with the registered monitoring plan, has the most conservative assumption theoretically possible been applied or has a request for deviation been approved?	All the data were available for the whole monitoring period.

DATA/PARAMETER	APJ
Data Unit	m ²
Description	Area of the reservoir measured in the surface of the water, after the implementation of the Project Activity, when the reservoir is full.
Source of data to be used	Scada System of the project
Value data for the monitoring period	524,023.35
Measuring and reporting frequency; recording procedure	Once for each monitoring period
Type of monitoring equipment and its accuracy	The parameter is monitored through the SCADA system of the Project Activity; therefore, measurement equipment is not used.
Calibration frequency/interval	NA
How were the values in the monitoring report verified and cross-checked?	The parameter is monitored through the google maps /13/ .
Does the data management (from monitoring equipment to emission reduction calculation) ensure correct transfer of data and reporting of emission reductions?	NA
If only partial data are available because activity levels or non-activity parameters have not been monitored in accordance with the registered monitoring plan, has the most conservative assumption theoretically possible been applied or has a request for deviation been approved?	All the data were available for the whole monitoring period.

Emission Reductions Achieved

The emission reductions calculation reported in the Monitoring Report version 03 of 19/01/2022 [/2/](#) and calculation spreadsheet “Final_ER calculations_538 Kumkoy hydro_v04_10-12-2019.xlsx” version 04 of 10/12/2019 [/8/](#) have been verified to be correct.

The emission reductions from the project for the monitoring period from 01/04/2019 to 02/03/2021 as reported in the Monitoring Report version 03 of 19/01/2022 [/2/](#) is equivalent to 83,484 tCO₂e. According to the registered VCS PD [/1/](#), the estimated emission reductions are equivalent to 98,343 tCO₂e per year. The reported averaged emission reductions are 15.1% lower than the estimated emission reduction. It is confirmed with the TEIAS meter readings [/15/](#) that there are no manual transposition errors between data sets have occurred.

4.5 Quality of Evidence to Determine GHG Emission Reductions and Removals

The generated electricity monitored continuously by two-unit meters that were sealed by TEIAS. Two electricity meters (one main meter and one backup meter) were installed at the project site. The old main meter was ACTARIS 53042294. The backup old meter was ACTARIS with serial number 53042295. The meters were changed on 20/10/2019.

The new main meter is ITRON with serial number 84260361. The backup new meter is ITRON with serial number 84260362.

The meters have the accuracy of 0.5s as confirmed through the meter change protocol [/19/](#). The accuracy class of the meters complies with the “Communiqué for Measurement Devices used in the Electricity Market” [/17/](#).

TEIAS is responsible for calibration and maintenance of the meters as per the registered VCS PD [/1/](#). The project owner has no control on the meters since the meters are sealed by the TEIAS as confirmed during the site visit. If any major discrepancy occurs between the two meters, TEIAS performs necessary calibration. The new meters at the project site were calibrated by the TEIAS on 20/10/2019 as confirmed through the meter change protocol [/19/](#).

As per the “Regulation of Metering and Testing of Metering Systems” [/18/](#), the meters shall be calibrated every 10 years, therefore the calibration of meters is deemed appropriate and in compliance with the national regulation. The calibration frequency has been respected.

The electricity generation figures are based on the TEIAS monthly meter readings /15/ and the EPIAS records /14/ are used for crosscheck from 01/04/2019 to 02/03/2021. The records and emission reduction calculation spreads sheet /8/ are consistent.

4.6 Non-Permanence Risk Analysis

There is no non-permanence risk rating determined by the project proponent.

5 VERIFICATION CONCLUSION

RINA Services Spa (RINA) has performed verification of the emission reductions reported for the project activity “Kumkoy Hydroelectric Power Plant, Samsun” in Turkey, VCS Registration Reference N° 986, for the period 01/04/2019 to 02/03/2021, with regard to the relevant requirements for CDM and VCS activities.

It is RINA’s opinion that the GHG emission reductions stated in the Monitoring Report version 03 of 19/01/2022 for the “Kumkoy Hydroelectric Power Plant, Samsun” project in Turkey for the period 01/04/2019 to 02/03/2021 are fairly stated. The GHG emission reductions were calculated correctly, on the basis of the approved monitoring methodology “ACM0002”, “Consolidated methodology for grid connected electricity generation”, version 13.0 of 11/05/2012 and the monitoring plan contained in the registered VCS PD.

Hence, RINA is able to certify that the emission reductions from the project during the monitoring period 01/04/2019 to 02/03/2021 amount to 83,484 tCO₂e.

Verification period: From 01/04/2019 to 02/03/2021

Verified GHG emission reductions and removals in the above verification period:

Year	Baseline emissions or removals (tCO ₂ e)	Project emissions or removals (tCO ₂ e)	Leakage emissions (tCO ₂ e)	Net GHG emission reductions or removals (tCO ₂ e)
01/03/2019 – 31/12/2019	38,184	0	0	38,184
01/01/2020 – 31/12/2020	42,055	0	0	42,055
01/01/2021 – 02/03/2021	3,245	0	0	3,245

Total	83,484	0	0	83,484
-------	--------	---	---	--------



CERTIFICATO DI QUALIFICA
QUALIFICATION CERTIFICATE

Si attesta che il sig./sig.ra:
We declare that Mr/Mrs/Ms:

Vinay SINGH

è qualificato come¹:
is qualified as:

TEC – VAL – VER – TL – ITRP – REG-EXP³

nello schema²:
for the scheme:

CDM – VCS – SCS – JI – ISO14064-2

per le seguenti aree tecniche:
for the following technical areas:

1.2 - 14.1

AREE TECNICHE TECHNICAL AREAS	DESCRIZIONE DELL'AREA TECNICA TECHNICAL AREA DESCRIPTION	SCOPO SETTORIALE SECTORAL SCOPE
1.2	Renewables	1
14.1	Forestry	14

In accordo alle istruzioni dell'Unità responsabile (OU) per sostenibilità & cambiamenti climatici.
in accordance with the instructions of the responsible unit (OU) for the sustainability & climate change.

REVISIONE REVISION	DATA DATE	MOTIVAZIONI PER LA REVISIONE REASON FOR THE REVISION
0	04/05/2020	First Issue
2	11/03/2022	Updated form

Il Resp. OU
Head of OU



¹ Legend:

VAL: Validator
VER: Verifier
TEC: Technical Expert
TL: Team Leader
FIN-EXP: Financial Expert
REG-EXP: Regional Expert
ITR: Independent Reviewer
DET: Determiner

² Legend:

CDM: Clean Development Mechanism
VCS: Verified Carbon Standard
GS4GG: Gold Standard for Global Goals
SCS: SocialCarbon Standard
JI: Joint Implementation
ISO14064-2: International standard 14064 part 2

³India, Kenya, Uganda, Sri Lanka, Thailand, Mauritius.

RINA Services S.p.A. è accreditata da UNFCCC, quale Entità Operativa Designata (DOE), per condurre la Validazione e la Verifica di Progetti CDM, da VCSA per condurre la Validazione e la Verifica di Progetti VCS, da GS Foundation, per condurre la Validazione e la Verifica di Progetti GS, da Ecologia Institute per condurre la Validazione e la Verifica di rapporti SCS.

RINA Services S.p.A. is accredited by the UNFCCC, as Designated Operational Entity (DOE), to carry out Validation and Verification of CDM Projects, by the VCSA, to carry out Validation and Verification of VCS Projects, by the GS Foundation, to carry out Validation and Verification of GS4GG Projects and by the Ecologia Institute, to carry out Validation and Verification of SCS Reports.

GHG_QUAL_CERT_EN(06-2021)

Page 1 of 1



CERTIFICATO DI QUALIFICA PER GLI SCHEMI VOLONTARI*
QUALIFICATION CERTIFICATE FOR VOLUNTARY SCHEMES*

Si attesta che il sig./sig.ra:
 We declare that Mr/Mrs/Ms:

Tugce Kiratli

è qualificato come:
 is qualified as:

TEC, VAL, VER, TL, ITRP
 LOCAL EXPERT

per le seguenti aree tecniche:
 for the following technical areas:

AREE TECNICHE TECHNICAL AREAS	DESCRIZIONE DELL'AREA TECNICA TECHNICAL AREA DESCRIPTION	SCOPO SETTORIALE SECTORAL SCOPE
1.2	Renewables	1
13.1	Solid waste and wastewater	13

REVISIONE REVISION	DATA DATE	MOTIVAZIONI PER LA REVISIONE REASON FOR THE REVISION
0	19/07/2016	First issue with new template
1	09/06/2017	Added qualification as ITRP and Local Expert

Responsabile di schema
 Scheme Leader
 Laura Severino



*SCHEMI VOLONTARI/ VOLUNTARY SCHEMES: ACR American Carbon Registry, CCB The Climate, Community & Biodiversity Alliance, GS Gold Standard, JI Joint Implementation, SCS Social Carbon Standard, VCS Verified Carbon Standard.

TEC: Technical expert; VAL: Validator; VER: Verifier; TL: Team leader; FIN EXP: Financial Expert; ITRP: Independent technical reviewer

RINA Services S.p.A. è accreditato/recognized da
 RINA Services S.p.A. is accredited /recognized by

UNFCCC	quali Entità Operativa Designata (DOE), per condurre la Validazione e la Verifica di Progetti CDM as Designated Operational Entity (DOE), to carry out Validation and Verification of CDM Projects
VCSA	per condurre la Validazione e la Verifica di Progetti VCS to carry out Validation and Verification of VCS Projects
GS Foundation	per condurre la Validazione e la Verifica di Progetti GS to carry out Validation and Verification of GS Projects
Ecologica Institute	per condurre la Validazione e la Verifica di rapporti SCS to carry out Validation and Verification of SCS Reports
American Carbon Registry ACR	per condurre la Validazione e la Verifica di Progetti ACR to carry out Validation and Verification of ACR projects
The Climate, Community & Biodiversity Alliance CCB	per condurre la Validazione e la Verifica di Progetti co-benefit CCB to carry out Validation and Verification of co-benefit CCB projects